



NASA CR-72691
ALRC-CE-44

SPACE STORABLE OXIDIZER VALVE

by

R. L. Crosier

AEROJET LIQUID ROCKET COMPANY
SACRAMENTO, CALIFORNIA 95813



Prepared for

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION

NASA Lewis Research Center
Contract NAS 3-12035
R. E. Grey, Project Manager

Reproduced by
NATIONAL TECHNICAL
INFORMATION SERVICE
U S Department of Commerce
Springfield VA 22151

| | | |
|-------------------|-------------------------------|---------------------------|
| FACILITY FORM 602 | <u>N71-38020</u> | <u>UAD</u> |
| | (ACCESSION NUMBER) | (THRU) |
| | <u>83</u> | <u>G3</u> ALRC |
| | (PAGES) | (CODE) |
| | <u>CR-72691</u> | <u>15</u> |
| | (NASA CR OR TMX OR AD NUMBER) | (CATEGORY) |

83p

NOTICE

This report was prepared as an account of Government-sponsored work. Neither the United States, nor the National Aeronautics and Space Administration (NASA), nor any person acting on behalf of NASA:

- A.) Makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately-owned right; or
- B.) Assumes any liabilities with respect to the use of, or for damages resulting from the use of, any information, apparatus, method or process disclosed in this report.

As used above, "person acting on behalf of NASA" includes any employee or contractor of NASA, or employee of such contractor, to the extent that such employee or contractor of NASA or employee of such contractor prepares, disseminates, or provides access to any information pursuant to his employment or contract with NASA, or his employment with such contractor.

Requests for copies of this report should be referred to

National Aeronautics and Space Administration
Scientific and Technical Information Facility
P.O. Box 33
College Park, Md. 20740

NASA CR-72691

ALRC-CE-44

SPACE STORABLE OXIDIZER VALVE

Prepared for

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION

31 August 1971

CONTRACT NAS 3-12035

Prepared by:

AEROJET LIQUID ROCKET COMPANY
P.O. Box 13222
Sacramento, California 95813

AUTHOR: R. L. Crosier
Project Engineer

APPROVED: O. D. Goodman
Program Manager

Technical Management:

NASA LEWIS RESEARCH CENTER
21000 Brookpark Road
Cleveland, Ohio 44135

APPROVED: R. E. Grey
Project Manager
Liquid Rocket
Technology Branch

FOREWORD

This final report describes the work accomplished by the Aerojet Liquid Rocket Company, Sacramento, California, under Contract NAS 3-12035. It covers the period 14 March 1969 through 30 July 1971. The contract was sponsored by the Lewis Research Center of the National Aeronautics and Space Administration. It was administered under the direction of the Liquid Rocket Technology Branch with Mr. R. E. Grey as Project Manager.

The author wishes to acknowledge the significant technical support contributed by the following:

| | |
|-----------------------|---|
| Materials Engineers: | Messrs. J. W. Chung and V. Hunt |
| Stress Analysis: | Mr. A. T. Caffo |
| Valve Design: | Mr. J. E. Dever |
| Seal Analysis: | Mr. F. M. Henson |
| Test Engineers: | Messrs. R. S. Simonsen, W. G. Hooper, and C. R. Crossman |
| Development Engineer: | Mr. A. Solter |

PRECEDING PAGE BLANK NOT FILMED

TABLE OF CONTENTS

| | <u>Page</u> |
|---|-------------|
| I. <u>SUMMARY</u> | 1 |
| II. <u>INTRODUCTION</u> | 2 |
| III. <u>TECHNICAL DISCUSSION</u> | 2 |
| A. VALVE DESIGN | 2 |
| 1. <u>Main Shutoff Seal</u> | 9 |
| 2. <u>Bellows</u> | 9 |
| 3. <u>Actuator</u> | 11 |
| 4. <u>Position Indicators</u> | 11 |
| 5. <u>Materials</u> | 13 |
| B. VALVE FABRICATION AND ACCEPTANCE TESTING | 17 |
| 1. <u>Fabrication</u> | 17 |
| 2. <u>Valve Assembly and Acceptance Testing</u> | 17 |
| C. FLUORINE COMPATIBILITY TESTING | 22 |
| 1. <u>Facility Preparation</u> | 22 |
| 2. <u>Operating Cycle and Proof Cycle Tests</u> | 27 |
| 3. <u>Valve Disassembly and Inspection</u> | 36 |
| IV. <u>DISCUSSION OF RESULTS</u> | 36 |
| V. <u>CONCLUSIONS</u> | 40 |
| VI. <u>RECOMMENDATIONS</u> | 40 |
| APPENDIX A. Compatibility Test Plan | 41 |
| APPENDIX B. Distribution List | 63 |

PRECEDING PAGE BLANK NOT FILMED

LIST OF TABLES

| <u>No.</u> | <u>Title</u> | <u>Page</u> |
|------------|--|-------------|
| I | Space Storable Oxidizer Valve Design Goals | 5 |
| II | Space Storable Oxidizer Valve Materials | 16 |
| III | Hardware Changes Required During Manufacture and Initial Assembly | 19 |
| IV | Acceptance Test Summary, Valve S/N 0000001 Incorporating Beryllium Nickel Seal | 20 |
| V | Acceptance Test Summary, Valve S/N 0000002 Incorporating Gold-Plated 304L Seal | 21 |
| VI | Fluorine Cycle Test Results - SSOV S/N 0000001 (Beryllium Nickel Seal) | 28 |
| VII | Fluorine Cycle Test Results - SSOV S/N 0000002 (Gold-Plated CRES 340L Seal) | 30 |
| VIII | Leakage Test Results - SSOV S/N 0000001 (Beryllium Nickel Seal) | 34 |
| IX | Leakage Test Results - SSOV S/N 0000002 (Gold-Plated CRES 304L Seal) | 35 |
| X | Test Instrumentation | 53 |

PRECEDING PAGE BLANK NOT FILMED

LIST OF FIGURES

| <u>No.</u> | <u>Title</u> | <u>Page</u> |
|------------|--|-------------|
| 1 | Angle Valve | 3 |
| 2 | Assembled View of Space Storable Oxidizer Valve (Poppet Illustrated in Open Position) | 7 |
| 3 | Exploded View of Space Storable Oxidizer Valve | 8 |
| 4 | Shutoff Seal/Seat Arrangement | 10 |
| 5 | Proximitior Probe Test Fixture | 12 |
| 6 | Proximitior Probe Output Voltage vs Temperature | 14 |
| 7 | Proximitior Probe Output Voltage vs Input Voltage | 15 |
| 8 | View of Flow Facility Showing Filter and Surge Dampener | 23 |
| 9 | Test Set-Up | 24 |
| 10 | View of LN ₂ Container Installed Around SSOV | 25 |
| 11 | Over-all View of Flow Facility with Return Line in Foreground | 26 |
| 12 | View of the Electrolyzed Inconel 718 Seat from SSOV S/N 0000001 after Fluorine Exposure | 37 |
| 13 | View of the Metal Seals after Fluorine Exposure | 38 |
| 14 | Cross Sectional View of Space Storable Oxidizer Valve | 50 |
| 15 | Test Setup Schematic | 51 |

ABSTRACT

The Space Storable Oxidizer Valve Program consisted of the design, fabrication, and testing of a 2.0-in., pneumatically-operated, metal-to-metal sealing, liquid fluorine shutoff valve. Two valve assemblies were subjected to liquid fluorine flow tests. These valves were identical in design and fabrication, but one incorporated a gold-plated CRES 304L main seal and the other had a beryllium nickel main seal. The beryllium nickel material transferred to the valve seat during testing. Of the two, the gold-plated seal proved to be more satisfactory in over-all performance.

I. SUMMARY

An Aerojet Liquid Rocket Company (ALRC) metal-to-metal sealing shutoff valve was evaluated by subjecting it to liquid fluorine testing. This design was developed in 1965 in a company-sponsored program. Its first use was an electrically-actuated all-metal valve in the Transtage Program.⁽¹⁾ The valve was adapted for the Space Storable Oxidizer Valve Program (SSOV) by replacing the electrical actuator with a pneumatic one.

Two main seal materials were evaluated by placing each in separate valve assemblies and testing them. Both seals were identical in design and fabrication except for the seal material itself which was beryllium nickel in one seal and gold-plated CRES 304L in the other seal.

Each valve was subjected to 250 liquid fluorine flow cycles; ten of these cycles at 25 psig (1.72×10^5 N/m², g) inlet pressure and the remaining 240 cycles at 100 psig (6.89×10^5 N/m², g) inlet pressure. After 250 cycles, the gold-plated CRES 304L seal demonstrated the superior performance and was subsequently subjected to an additional 756 liquid fluorine flow cycles at a proof inlet pressure of 250 psig (1.72×10^6 N/m², g). All the tests were conducted satisfactorily without damage to the test hardware.

Both valves operated satisfactorily throughout the test program. Valve pressure drop was under that required and valve actuation times were easily controlled by orificing the actuator helium supply and vent lines. The valve bellows, actuator assemblies, and the proximator probes were in good condition at the end of testing. The gold-plated seal also was in good condition; however, seal standoff, which is a setting made during valve assembly to control the sealing load on the seal, decreased 48% during the testing. This caused the seal load to become relaxed and resulted in a final gold-plated seal leakage rate of 1.00×10^{-1} SCCS helium at 250 psig (1.72×10^6 N/m², g) and -320°F (77.6°K) after 1006 fluorine cycles.

All valve materials performed as anticipated except for the beryllium nickel seal material which transferred to the electrolized Inconel 718 seat. This occurred early in the program and resulted in increased leakage through the tenth fluorine cycle. At this point, the seal started to lap into the seat and leakage decreased steadily through the end of the program. The final beryllium nickel seal leakage rate of 2.44 SCCS helium at 250 psig (1.72×10^6 N/m², g) and -320°F (77.6°K) after 250 fluorine cycles was approximately one-half that measured after the tenth cycle.

The beryllium nickel material transfer and the loss of the gold-plated seal standoff caused the leakages noted during the program.

It was concluded that the CRES 304L material is not satisfactory for this type of seal because of material instability. A gold-plated beryllium nickel seal would incorporate the best features of both the seals tested and should provide excellent service in a fluorine valve. The beryllium nickel material would maintain the set standoff adjustment, as it did during the testing in this program, and the gold plating would prevent the transfer of the beryllium nickel material.

(1) CCN 192, "Electrical Valve Development, Contract AF 04(695)-197, Transtage Program, 15 February 1967.

II. INTRODUCTION

The feasibility of using fluorinated oxidizers in space vehicles has been under investigation for almost 20 years. Recent programs⁽²⁾⁽³⁾ established design criteria for a fluorine lightweight feed system with primary emphasis upon valve compatibility and leakage. These studies again showed the importance of achieving extremely low leakage rates throughout a fluorine system.

ALRC conducted a company-sponsored program in 1965 to develop a reliable all-metal shutoff seal for future space propulsion systems. Successful test results were obtained with the design evolved and served as the basis in selecting this configuration for use in an all-metal bipropellant valve developed under an Air Force contract.⁽⁴⁾ It was this same basic valve design configuration that was tested in the SSOV Program.

The SSOV Program was conducted under Contract NAS 3-12035 for the purpose of evaluating the existing ALRC metal-to-metal seal design with regard to leakage and to determine which of two different seal materials is the better for fluorine service. The program consisted of the design, fabrication and test of the pneumatically actuated SSOV and was organized into three tasks.

The design task consisted primarily of adapting the pneumatic actuator to the existing ALRC valve design. The fabrication and acceptance test task covered the manufacture and acceptance testing of two valves while the fluorine compatibility test task consisted of flow testing the valves in liquid fluorine.

This report is organized on the basis of these three tasks with the information being presented in the order in which the tasks were accomplished. Appendix A presents the detailed test plan under which the fluorine compatibility testing was accomplished.

It is believed that the information presented in this report will be of value to others when further work on a lightweight fluorine feed system is pursued as the experience gained in this program and will give direction for future improvements in fluorine valve sealing and actuation.

III. TECHNICAL DISCUSSION

A. VALVE DESIGN

The Space Storable Oxidizer Valve (Figure 1) is a 2.0-in. (15.08 x 10⁻² m) pneumatically-operated, liquid fluorine shutoff valve of right angle flow design. The inlet port is located at one end of the valve and the actuator is in-line opposite this port. A welded, nested-type bellows is welded to the valve body and seals the actuator cavity from the flow path. Actuator force is applied directly to the end of the bellows shaft by pressurizing the pneumatic actuator with helium. Two position indicators are used to monitor the full-open and full-closed positions of the valve. The valve was designed to meet the goals delineated on Table I. Figures 2 and 3 are the assembled and exploded views of the valve, respectively.

(2) Contract NASw-1351, Development and Demonstration of Criteria for Liquid Fluorine Feed System Components, Douglas Aircraft Company, October 1967.

(3) Contract NAS 3-11195, Development and Demonstration of Criteria for Liquid Fluorine Feed System Components, McDonnell Douglas Astronautics Company, June 1969.

(4) CCN 192, Contract AF 04(695)-197, op. cit.

NOT REPRODUCIBLE

Figure 1. Angle Valve
(Sheet 1 of 2)




Figure 1. Angle Valve
(Sheet 2 of 2)

TABLE I. - SPACE STORABLE OXIDIZER VALVE DESIGN GOALS

FLUID SPECIFICATIONS:

1. Liquid Oxygen (MIL-O-25508)
2. Liquid Fluorine (98.7% LF_2 , min)
(0.3% [by wt.] max, HF, CH_4)
(1.0% [by wt.] max O_2 , N_2 , other inerts)
3. Mixtures of (1) and (2)
4. Helium (Grade A Bureau of Mines)
5. Liquid Nitrogen (MIL-P-27401)

TEMPERATURE:

Inlet Fluid -320°F (77.6°K)

FLUID PRESSURE:

Oxidizer 100 psig ($6.89 \times 10^5 \text{ N/m}^2$, g) max operating
 250 psig ($1.72 \times 10^6 \text{ N/m}^2$, g) proof
 375 psig ($2.58 \times 10^6 \text{ N/m}^2$, g) burst

ACTUATION:

Helium 500 psig ($3.45 \times 10^6 \text{ N/m}^2$, g) max operating
 750 psig ($5.17 \times 10^6 \text{ N/m}^2$, g) proof
 1125 psig ($7.76 \times 10^6 \text{ N/m}^2$, g) burst

FLOW RATE: 60 gpm ($3.78 \times 10^{-3} \text{ meter}^3/\text{second}$)

PRESSURE DIFFERENTIAL AT RATED FLOW: 5 psid ($3.45 \times 10^4 \text{ N/m}^2$)

LINE SIZES: 2 in. ($5.08 \times 10^{-2} \text{ m}$) ID

LEAKAGE RATE:

1. Between propellant and actuator zero sccm He
 ($1 \times 10^{-6} \text{ SCCS He}$)
2. Main seat leakage 10^{-7} pps F_2
 ($2.50 \times 10^{-2} \text{ SCCS F}_2$)
 ($2.83 \times 10^{-2} \text{ SCCS F}_2$)

TABLE I (cont.)

MATERIAL:

Only metallic fluoride lubricants to be permitted in the propellant cavities.

ACTUATION TIME (MAXIMUM):

75 millisec

ENVIRONMENTAL CONDITIONS:

1. This valve shall be designed to be functioning properly with ambient pressure from 0 psia to 14.7 psia ($1.01 \times 10^5 \text{ N/m}^2$), ambient temperature of -250°F (116.7°K) to $+140^\circ\text{F}$ (333.3°K), humidity from 0% to 100%, vibrations $\pm 0.25 \text{ in.}$ ($6.35 \times 10^{-3} \text{ m}$) amplitude from 5 cps to 31 cps, and 25 g's from 31 cps to 2000 cps. No test verification shall be required.
2. Accelerations:

12.0 g's parallel and perpendicular.

No test verification shall be required.

SPECIAL CONSIDERATIONS:

1. The valves shall be designed for maximum internal passivation with fluorine gas.
2. Positive isolation shall be provided between propellant and actuator. Redundancy shall be considered.
3. The valve shall fail safe closed under normal operating conditions.




Figure 2. Assembled View of Space Storable Oxidizer Valve
(Poppet Illustrated in Open Position)

NOT REPRODUCIBLE

8




Figure 3. Exploded View of Space Storable Oxidizer Valve

1. Main Shutoff Seal


The valve features a metal-to-metal, hard-on-soft, seat-seal design (see Figure 4). The shutoff seal consists of a thin, spherical, metal shell which seats in a conical seat that is machined as an integral part of the valve body. In operation, the flexible seal contacts and centers itself in the valve seat as the valve closes. Then, the poppet assembly travels an additional distance (0.004-in. to 0.005-in.) (1.02×10^{-4} m to 1.27×10^{-4} m) into the seat until travel is halted by a conical metal stop provided on the poppet guide. This additional poppet travel provides a wiping, or lapping, action between the seal and seat to produce a microscopic conformation of the two sealing surfaces. At the same time, deflection of the seal provides the preload required to prevent leakage.

The seal and poppet guide are assembled prior to installation into the valve. Shims are installed between the guide and seal (see Figure 4) to adjust the relationship between the sealing edge and the stop on the guide. The amount that the seal projects beyond the surface of the stop in the free condition is the adjusted seal standoff, which is adjusted to a maximum of 0.002-in. (5.08×10^{-5} m) for 300 series CRES seals and 0.0025-in. (6.35×10^{-5} m) for beryllium nickel seals. Also, the guide can be installed in 12 different positions around the seal shaft to minimize any eccentricity in the assembly. This is accomplished by rotating the seal until the minimum eccentricity is obtained between the seal and guide stop. Then the assembly is locked with a locking strip installed between one of 12 slots in the end of the guide and a slot in the seal shaft.

One of the basic requirements in the design of the SSOV was the capability for eliminating all threads exposed to the flow stream. Threads would be acceptable in the demonstration valve but not in a production version. This requirement dictated that the materials utilized in the seal and poppet guide be weldable. Therefore, the final materials selected for the two test seals were CRES 304L and beryllium nickel 440 temper A. The poppet guide is made from CRES A286. Experience with the CRES 304L material made known that it could gall during usage if tested in the unprotected state. Consequently, the spherical surface of the CRES 304L seal was gold-plated using the electro-deposition process to 0.0015-in. (3.81×10^{-5} m) thick. Following plating, the gold was polished to a 2 microinch AA (5.08×10^{-8} m AA) surface finish with a minimum thickness of 0.0005-in. (1.27×10^{-5} m).

2. Bellows

The poppet shaft extends through the valve body and is sealed by a single ply (0.006-in. thick) (1.52×10^{-4} m) nesting type of welded bellows. One end of the bellows is welded to the shaft and the other end is welded to the valve body. Two keys are provided to prevent rotation of the bellows when the shaft attachment nuts are tightened or from the torque produced by compression of the valve springs. The keys also provide a stop to



SHUTOFF SEAL CONSISTS OF A THIN, SPHERICAL SHELL SEATED IN THE CONICAL SEAT PORTION OF THE VALVE BODY.

DURING CLOSURE THE SEAL CONTACTS AND CENTERS ITSELF IN THE SEAT.

A WIPING OR LAPPING ACTION BETWEEN SEAL AND SEAT PRODUCED MICROSCOPIC CONFORMATION OF THE SEALING SURFACES.

DEFLECTION OF THE SEAL PROVIDES THE SEALING PRELOAD.

EXCESSIVE SEAL DEFLECTION IS PREVENTED BY ACCURATELY LIMITING THE DEFLECTION WITH THE STOP.

Figure 4. Shutoff Seal/Seat Arrangement

prevent overextension of the bellows during inspection and fabrication assuring that the bellows convolutions are always in compression. These keys, which are an integral part of the bellows end fitting, ride in keyways in the valve shaft. Adverse pressure effects are minimized by externally pressurizing the bellows as well as locating it downstream of the shutoff seal.

A means for cleaning the bellows without disassembly of the valve is provided as an integral part of the valve. This is accomplished by introducing cleaning fluid into a cavity formed by the body and a thin stainless steel sleeve held in the body by a shrink-fit at each end. The fluid is sprayed onto the bellows through four rows of holes located 90-degrees apart in the sleeve. The holes in each row are arranged so that each convolution of the bellows passes at least one hole in the row when the valve is actuated. The fluid then passes out of the valve through the valve outlet port.

3. Actuator

A pneumatic actuator was designed to replace the electrical actuator used in the Transtage version of the valve. The poppet return spring and spring guide were retained. A piston and housing were added to complete the pneumatic actuator assembly. The piston bears against the spring guide and pushes the valve open when energized by helium pressure. This piston is guided in the actuator housing and is sealed by a spring-loaded Teflon dynamic seal. The valve stroke of 0.500 ± 0.002 -in. ($1.27 \times 10^{-2} \pm 5.08 \times 10^{-5}$ m) is controlled by the end of the spring guide contacting against the valve body. Adjustment of the stroke is provided by shims installed between the main shutoff seal and the bellows shaft (View A on Figure 1).

4. Position Indicators

Proximitors are used as the valve position indicators. These devices sense the edge of a CRES 347 stainless steel washer as it passes the face of the probe at each end of the valve stroke. This concept was known to be practical at room temperature; however, the effect of a cryogenic environment upon the probe output signal was not known. Tests were conducted to establish a correlation between the output voltage at room temperature and the output at cryogenic temperature.

A test fixture (see Figure 5) was borrowed from the probe supplier (Bently Nevada Corporation of Minden, Nevada) and utilized for the tests. As the micrometer was turned, the washer moved from one side of the probe to the other, similar to the actual valve design. Tests were performed at ambient and cryogenic temperatures at gap settings of 0.0065-in. (1.65×10^{-4} m) to greater than 0.060-in. (1.52×10^{-3} m), and at input voltages of -18, -24, and -28 vdc. A Bently Nevada proximitors (P/N 3106) was used to provide energy to the probe.




Figure 5. Proximity Probe Test Fixture

Test results showed a definite reduction in the output signal when the probe was immersed in liquid nitrogen. A CRES 347 stainless steel washer and an input voltage of -18 vdc were used. The output reduction at low temperature ranged from 42% to 44% of the room temperature voltage output for large gaps greater than 0.060-in. (1.52×10^{-3} m) to 56% for a gap of approximately 0.010-in. (2.54×10^{-4} m). Figure 6 contains comparison curves between the room temperature and LN₂ tests conducted at -18 vdc. Curves from data taken at -18, -24, and -28 vdc are shown on Figure 7.


Comparison of the probe output signals indicated that the probe could not be adjusted to give consistent output voltage readings over the entire valve operating temperature ranging of +140°F to -320°F (33.1°K to 77.6°K). However, it was concluded that the standard design probe would give an adequate valve position trace at the ends of the valve stroke if the input voltage was set high and the gap setting between the probe and washer was kept as small as possible. In the SSOV design, the gap was specified as 0.004-in. to 0.006-in. (1.02×10^{-4} m to 1.52×10^{-4} m) and the voltage as -18 vdc minimum with -28 vdc preferred.

5. Materials

Fluorine is one of the most powerful oxidizing agents known and can react with practically all organic and inorganic substances. Therefore, the principal criteria for the selection of materials for liquid fluorine service are propellant compatibility and the retention of ductility as well as toughness at the service temperature. Materials must have the capability to be passivated through the formation of a protective fluoride film, a low uniform corrosion rate in the propellant, and high resistance to stress corrosion cracking. All of the materials that are exposed to liquid fluorine in the space storable oxidizer valve have the capability for meeting all of the above requirements.

The valve materials are listed on Table II. The mechanical property requirements of the valve materials exposed to fluorine were satisfied by selecting non-heat treatable as well as heat-treatable stainless steels and nickel base alloys. The 304L stainless steel and Inconel 600 have intermediate strength as well as excellent ductility along with toughness at ambient and cryogenic temperatures. The alloys A-286, Inconel 750, and Inconel 718 provide high yield strength in the range of 100 ksi to 160 ksi (6.89×10^8 N/m² to 1.10×10^9 N/m²) with attendant good ductility at ambient and cryogenic temperatures.

Welding requirements include tungsten inert gas (TIG) weldments of Inconel 750 to itself and to Inconel 600 as well as electron-beam weldment of Inconel 600 to Inconel 718. All of these materials are readily weldable with the exception of Inconel 750, which is considered to possess good weldability in thin sections only. However, in the valve application, Inconel 750 is used as the bellows and good welding characteristics have been demonstrated.






Figure 7. Proximitors Probe Output Voltage vs Input Voltage

TABLE II. - SPACE STORABLE OXIDIZER VALVE MATERIALS

| <u>Part No.</u> | <u>Nomenclature</u> | <u>Material</u> |
|-----------------|-------------------------|--------------------------------|
| *1157214 | Washer Positioning Nut | Aluminum Alloy 6061-T6** |
| 1157215-1 | Main Shutoff Seal | CRES 304L, gold plated |
| 1157215-2 | Main Shutoff Seal | Beryllium Nickel 440, Temper A |
| 1157216 | Bellows Cleaning Sleeve | CRES 304L |
| 1157217 | Push Rod (Bellows) | |
| | End Plate | Inconel Alloy 600 |
| | Shaft | Inconel Alloy 718 |
| | Bellows Disks | Inconel Alloy 750 |
| 1157218 | Body | Inconel Alloy 718 |
| | Seat | Electrolize chrome plating |
| *1157221 | Actuator Piston | Aluminum Alloy 6061-T6 |
| *1157222 | Actuator Housing | Aluminum Alloy 6061-T6 |
| *1157223 | Actuator Seal Retainer | Aluminum Alloy 6061-T6 |
| *1157224 | Probe Sensing Washer | CRES 347 |
| *1157471 | Return Spring | CRES 17-7PH |
| 1157472 | Shims | CRES 301 |
| 1157474 | Key Tab Washer | CRES 304 |
| 1157475 | Poppet Guide | CRES A286 |
| 1157476 | Locking Strip | CRES 304 |
| *1157477 | Spring Retainer | Inconel Alloy 718 |

*Not exposed to fluorine.

**Changed to Teflon (see Table III).

B. VALVE FABRICATION AND ACCEPTANCE TESTING

SSOV hardware was manufactured in the Mechanical and Optical Fabrication Shops, Aerojet Electronics Division, Azusa, California and at selected vendor facilities. Valve assembly and acceptance testing were accomplished in the ALRC Engineering Laboratories. Details of the fabrication, assembly, and acceptance test efforts are discussed below.

1. Fabrication

Two hardware anomalies were accepted prior to the start of assembly; one bellows shaft exhibited a low material hardness and two valve bodies had rough seat finishes. The bellows shaft hardness measured Rockwell C-35.5 instead of a specified Rc-38 minimum. Stress calculations were performed to verify the usability of the shaft, which had an adequate margin of safety, was accepted, and was used throughout the test program without incident.

Valve bodies were received at ALRC with seat finishes of 8 microinches AA (2.03×10^{-7} m AA) instead of the specified 2 microinches AA (5.08×10^{-8} m AA). The body supplier stated that he had measured the seat finish as 2 microinches AA (5.08×10^{-8} m AA) prior to plating but had not measured the finish after the electroplate operation. The effect of electroplating on the surface finish was determined on a flat specimen. Plating increased the measurement a maximum of one microinch (2.54×10^{-8} m AA) when applied to a 2 to 3 microinch AA (5.08×10^{-8} to 7.62×10^{-8} m AA) surface. The supplier specified that this was his best effort and that any rework would have to be performed by a microfinished company.

Because of time and cost factors as well as the possibility that the seats might be damaged if rework was attempted, an investigation was conducted to determine the usability of the existing bodies. Calculations performed to determine the effect of the 8 microinch AA (2.03×10^{-7} mm AA) finish upon leakage verified that leakage would approach the specified rate; however, this was acceptable. The seat surface finish of one of the valve bodies that had performed satisfactorily in the Transtage program was measured at 7 microinches AA (1.78×10^{-7} m AA). Based upon this information and the knowledge that the seal finishes were much better than that specified, the bodies were accepted without rework.

2. Valve Assembly and Acceptance Testing

Valve assembly was initiated by electron-beam welding the bellows assembly into the valve body. All subsequent assembly operations were accomplished on a laminar flow bench in the Engineering Controls Laboratory. All hardware was cleaned to Level "E" (oxidizer clean) in accordance with Specification AGC-46350(5) prior to any assembly work, including the

(5) ALRC Process Specification AGC-46350, "Levels of Cleanliness,"
20 February 1964.

electron-beam welding operation. Clean, lint-free gloves were worn during all assembly operations. Two identical valve assemblies were built for the seal in each except a beryllium nickel seal (Valve S/N 0000001) was used in one and a gold-plated CRES 304L seal (Valve 0000002) was used in the other.

Several minor changes were made to the valve hardware during initial assembly and testing. Most involved the addition of chamfers to facilitate assembly and seal installation. All the changes made are shown on Table III. One revision required a change in the shape and material of the large nut utilized to position the proximator probe washer on the end of the actuator piston. Aluminum chips were discovered in the smaller bore of the actuator housing during the disassembly needed to reposition the washer. The washer had contacted the housing during valve actuation and could not be positioned accurately enough to prevent this rubbing.

The positioning nut, P/N 1157214-1, was replaced with a round teflon nut that was a close fit (0.002-in. to 0.007-in. [5.08×10^{-5} in. to 1.78×10^{-4} m] on the diameter) in the actuator housing. The outside diameter of the washer was reduced to a size 0.003-in. to 0.008-in. (7.62×10^{-5} m to 2.03×10^{-4} m) smaller than the nut. During assembly, the washer was positioned in a manner assuring that no portion extended beyond the edge of the nut. This change eliminated the rubbing between the washer and housing while permitting an accurate adjustment of the proximator probes.

Acceptance tests were conducted at both ambient and cryogenic temperatures (see Tables IV and V for test results). The valve actuation system consisted of two, two-way pilot valves with one of the pilot valves connected to each leg of a tee at the actuator. The opening orifice was installed immediately upstream from the opening pilot valve in the pressurization line and the closing orifice was installed upstream from the closing pilot valve, between the closing pilot valve and the tee. This arrangement gave a hard system with the orifices pressurized before the actuation of the respective pilot valve. Both pilot valves were actuated simultaneously by the same signal. This system resulted in more predictable and repeatable valve actuation times than was possible with a single, three-way pilot valve with the closing orifice mounted downstream from the pilot valve.

The gold-plated seal leaked in excess of the specified rate at cryogenic temperature during the main seal internal leakage test. It was not known at the time, but the seal had not yet "seated" into the body. The valve was accepted for test and installed in the flow facility for fluorine testing. After numerous test set-up and instrumentation checkout cycles, the seal "seated" and leakage was within the specified rate of 2.5×10^{-3} SCCS when the post-facility installation leakage test was conducted.

The actuation piston seal in both valve assemblies leaked in excess of the original value specified, but in no way affected valve actuation during acceptance testing or the fluorine test cycles. It is believed that

TABLE III. - HARDWARE CHANGES REQUIRED DURING MANUFACTURE
AND INITIAL ASSEMBLY*

| <u>Part</u> | <u>Part No.</u> | <u>Change</u> |
|-------------------|---|--|
| Nut, Positioning | 1157214-1 (Item No. 13 on 1157220) | Add -2 part made from Teflon FEP with an OD of 0.747/0.744-in. (1.897×10^{-2} / 1.889×10^{-2} m), notched for free helium flow. |
| Seal | 1157215-1, -2 (Item Nos. 14 and 21 on 1157220) | Add a thermal stabilization process to rough machine within 0.020-in. (5.08×10^{-4} m), then conduct 10 thermal cycles of immersing the seal in LN ₂ for 5 minutes, then in tap water until the seal is warm. The seals shall then be finish machined. |
| Housing, Actuator | 1157222-1, -3 (Item Nos. 17 and 44 on 1157220) | Add a 0.045-in. (1.14×10^{-3} m) \times 45° chamfer on the inner corner of the seal groove at the large end of the housing. Add a 0.015-in. (3.81×10^{-4} m) radius at the intersection of the 0.751/0.749-in. (1.907×10^{-2} / 1.902×10^{-2} m) diameter bore (small bore in the housing) and the 30-degree chamfer into the large bore. |
| Washer | 1157224-1 (Item No. 19 on 1157220) | Change OD to 0.741/0.739-in. (1.882×10^{-2} / 1.877×10^{-2} m). |

*See Figure 1 for the location of each part.

TABLE IV. - ACCEPTANCE TEST SUMMARY, VALVE S/N 0000001 INCORPORATING BERYLLIUM NICKEL SEAL

| <u>Operation</u> | <u>Conditions</u> | <u>Objectives</u> | <u>Results</u> |
|---------------------------------|---|-----------------------------|--|
| Proof Test | 400 psig LN ₂ (2.76×10^6 N/m ² , g) | No permanent deformation | No permanent deformation |
| | 750 psig HE (5.17×10^6 N/m ² , g) | | |
| Bellows Proof Test | 250 psig LN ₂ (1.72×10^6 N/m ² , g) | 75 actuations | 75 actuations |
| | 500 psig HE (3.45×10^6 N/m ² , g) | 1×10^{-6} scc/sec | 1.24×10^{-9} scc/sec |
| Functional Test | 250 psig LN ₂ (1.72×10^6 N/m ² , g) | 50-75 msec | 70 msec open |
| | 500 psig HE (3.45×10^6 N/m ² , g) | Open and Close | 50 msec close |
| Internal Leak Test Main Seal | 250 psig HE (1.72×10^6 N/m ² , g) Ambient Temperature | 25×10^{-3} scc/sec | 2.66×10^{-3} scc/sec |
| Main Seal | 250 psig HE (1.72×10^6 N/m ² , g) LN ₂ Temperature | 25×10^{-3} scc/sec | 3.40×10^{-3} scc/sec |
| Piston Seal | 500 psig HE (3.45×10^6 N/m ² , g) | 25×10^{-3} scc/sec | 1.20×10^{-1} scc/sec |
| External Leak Test | 250 psig HE (1.72×10^6 N/m ² , g) Ambient Temperature | 25×10^{-4} scc/sec | Zero scc/sec inlet and outlet flanges |
| | 250 psig HE (1.72×10^6 N/m ² , g) LN ₂ Temperature | 25×10^{-4} scc/sec | Zero scc/sec inlet and outlet flanges |

TABLE V. - ACCEPTANCE TEST SUMMARY, VALVE S/N 0000002 INCORPORATING GOLD-PLATED 304L SEAL

| <u>Operation</u> | <u>Conditions</u> | <u>Objectives</u> | <u>Results</u> |
|---------------------------------|---|---|--|
| Proof Test | 400 psig LN ₂ (2.76×10^6 N/m ² , g) 750 psig HE (5.17×10^6 N/m ² , g) | No permanent deformation | No permanent deformation |
| Bellows Proof Test | 250 psig LN ₂ (1.72×10^6 N/m ² , g) 500 psig HE (3.45×10^6 N/m ² , g) | 75 actuations 1×10^{-6} scc/sec | 75 actuations 1.4×10^{-10} scc/sec |
| Functional Test | 250 psig LN ₂ (1.72×10^6 N/m ² , g) 500 psig HE (3.45×10^6 N/m ² , g) | 50 - 75 msec Open and close | 70 msec open 50 msec close |
| Internal Leak Test Main Seal | 250 psig HE (1.72×10^6 N/m ² , g) Ambient Temperature. | 25×10^{-3} scc/sec | 1.70×10^{-2} scc/sec |
| Main Seal | 250 psig HE (1.72×10^6 N/m ² , g) LN ₂ Temperature | 25×10^{-3} scc/sec | 1.50×10^{-1} scc/sec |
| Piston Seal | 500 psig HE (3.45×10^6 N/m ² , g) | 25×10^{-3} scc/sec | 6.70×10^{-2} scc/sec |
| External Leak Test | 250 psig HE (1.72×10^6 N/m ² , g) Ambient Temperature | 25×10^{-4} scc/sec | 1.16×10^{-6} scc/sec (out) 2.32×10^{-7} (scc/sec (in) |
| | 250 psig HE (1.72×10^6 N/m ² , g) LN ₂ Temperature | 25×10^{-4} scc/sec | 2.15×10^{-7} scc/sec (out) 1.44×10^{-7} scc/sec (in) |
| | | | Out = outlet flange In = inlet flange |

the leakage objective of this seal was too rigid in view of the particular installation and the cryogenic conditions to which the seal was subjected. If the actuator was redesigned for flight use, this plastic seal would be replaced with a metal seal (i.e., a bellows).

C. FLUORINE COMPATIBILITY TESTING


The two space storable oxidizer valves were tested in the fluorine test facility, Test Stand J-4A, at Sacramento, California. This stand, which is used primarily for the performance testing of valves, pumps, bearings, and seals with liquid fluorine or Flox, is equipped with a conventional, pressure-fed, remote-controlled, flow loop. It also has a charcoal pit for the disposal of vented fluorine and fluorine-compounds as well as deluge systems to protect the stand from any fire damage resulting from spillage. Visual observation of the stand and flow system during testing is accomplished by means of closed-circuit television.

1. Facility Preparation

The facility flow loop was modified for SSOV testing by installing a 2.0-in. (5.08×10^{-2} m) fluorine filter, adding a parallel flow loop for concurrent testing of both valves, and adding a surge dampener upstream from the valves. The filter, a Wintec Model No. 54241-508, is shown on the lower left-hand corner of Figure 8. The jacketed and insulated surge dampener is installed vertically immediately downstream from the filter. The fluorine system is jacketed up to the filter inlet; these jackets and the jacket around the surge dampener were filled with LN₂ prior to each flow test. Figure 9 is the test schematic.

Sheet metal containers were fabricated and installed around the two test valves. These containers were sealed at the inlet and outlet flanges as well as around the actuator covers. They were filled with liquid nitrogen prior to each cryogenic leak test to maintain a valve temperature of -300°F (88.7°K) maximum. This method of chilling the valve was effective as long as the liquid nitrogen level was maintained with the valve assembly submerged. One of the containers with the lid removed is shown on Figure 10. A closed container is visible on Figure 11, which is an over-all view of the flow test set-up.

The pilot valves shown mounted on the small blastshield between the SSOV's on Figures 8, 10 and 11 were relocated to be close-coupled with the SSOV actuators. The long line lengths shown delayed valve opening and closing as compared to the times obtained during acceptance testing. Also, the potentiometers projecting from the ends of the valve actuators were affected by the cold when the valves were thoroughly chilled. The potentiometers were wrapped with heater blankets and then operated satisfactorily. These potentiometers were added test equipment used to supplement and verify the proximator probe readings.



NOT REPRODUCIBLE

Figure 8. View of Flow Facility Showing Filter and Surge Dampener





Figure 9. Test Set-Up



NOT REPRODUCIBLE

Figure 10. View of LN_2 Container Installed Around SSOV




Figure 11. Over-all View of Flow Facility with Return Line in Foreground

2. Operating Cycle and Proof Cycle Tests

SSOV S/N 0000001 (beryllium nickel seal) was subjected to 250 liquid fluorine flow cycles and SSOV S/N 0000002 was subjected to 1006 liquid fluorine flow cycles in accordance with the SSOV Compatibility Test Plan (see Appendix A). The first ten cycles were conducted with an inlet pressure of 25 psig (1.72×10^5 N/m², g) and the following 240 cycles were conducted with an inlet pressure of 100 psig (6.89×10^5 N/m², g). At this point, the valve with the gold-plated CRES 304L seal showed better leakage results. Therefore SSOV (SN 0000002) was selected for further testing and subjected to 756 flow cycles at a proof inlet pressure of 250 psig (1.72×10^6 N/m², g).

During the first flow cycles, it was noted that the initial flow through the valve was being supplied completely from the surge dampener. This caused a delay in flow throughout the system and a corresponding delay in the flow-meter signal. At shutdown, system flow continued until the surge dampener was repressurized to system pressure. This phenomenon had little effect upon the flow results at 25 psig (1.72×10^5 N/m², g); however, a pressure spike was noted downstream from the valve poppet during initial valve opening. This spike was caused by the high flow being restricted by the stand valve installed immediately downstream from the SSOV. This close-coupled valve was part of the minimum volume leakage measurement system used to collect and measure SSOV poppet leakage.

During testing at 100 psig (6.89×10^5 N/m², g), pressure spikes as high as 181 psig (1.25×10^6 N/m², g) were measured at the stand valve inlet flange during SSOV opening. It was apparent that testing at 250 psig (1.72×10^6 N/m², g) would be impossible under these conditions without damaging the SSOV bellows. Therefore, with the concurrence of the NASA-LeRC Project Manager, all cycles conducted at 250 psig (1.72×10^6 N/m², g) inlet pressure were performed with the pressure balanced across the valve poppet prior to valve opening. System valves were sequenced in a manner that the SSOV was subjected to full flow rate and full pressure shutdown as originally scheduled.

Test cycle results are presented on Tables VI and VII. Leakage data are presented on Tables VIII and IX. Each valve was subjected to approximately 255 purge, functional checkout, instrumentation checkout, and passivation cycles before the first fluorine flow cycle. During these initial cycles, the gold-plated seal seated and the leakage rate of SSOV S/N 0000002 improved to less than the specified leakage rate by the time that the first fluorine flow cycle was accomplished. At the same time, the leakage rate of SSOV S/N 0000001, which incorporated the beryllium nickel seal, deteriorated to an out-of-specification condition before the first fluorine flow cycle. Performance of the beryllium nickel seal did not improve significantly throughout the flow test although the leakage after 250 cycles was only one-half of the leakage measured after the tenth cycle. Gold-plated seal leakage was

TABLE VI. - FLUORINE CYCLE TEST RESULTS - SSOV S/N 0000001 (BERYLLIUM NICKEL SEAL)

| Test No. (1334-D01-OV-XXX) | Duration-sec | Tank Pressure-psig | Actuation Pressure-psig | Inlet Temperature °F | Flow lb/sec | Opening Time-MS Orifice-inches | Closing Time-MS Orifice-inches | |
|----------------------------|--------------|--------------------|-------------------------|----------------------|-------------|--------------------------------|--------------------------------|-----------|
| Pre-test functional | - | 25 He | 250 | ambient | - | 230/0.030 | 270/0.045 | |
| Pre-test functional | - | 100 He | 250 | ambient | - | 160/0.030 | 290/0.045 | |
| Pre-test functional | - | 250 He | 250 | ambient | - | 120/0.030 | 270/0.045 | |
| Pre-test functional | - | 250 He | 350 | ambient | - | 85/0.030 | 270/0.045 | |
| Test No. | Cycle No. | | | | | | | |
| 004 | 1 | 113 | 28 LF ₂ | 250 | -284 | 2.59 | 90/0.030 | 170/0.045 |
| 006 | 2 | 20 | 30 LF ₂ | 250 | -280 | * | 85/0.030 | 170/0.045 |
| 009 | 4 | | 31 LF ₂ | 250 | -283 | 2.76 | 105/0.030 | 185/0.045 |
| | 10 | 160 | 29 LF ₂ | 250 | -290 | 3.16 | 102/0.030 | 180/0.045 |
| 011 | 11 | | 100 LF ₂ | 250 | -285 | 6.14 | 80/0.033 | 70/0.065 |
| | 49 | | | | -285 | 6.45 | 75/0.033 | 72/0.065 |
| | 50 | 160 | | | -285 | 6.44 | 75/0.033 | 74/0.065 |
| 012 | 51 | | | | -287 | 6.27 | 75/0.033 | 70/0.065 |
| | 52 | | | | -287 | 6.40 | 77/0.033 | 70/0.065 |
| | 99 | | | | -287 | 6.48 | 80/0.033 | 75/0.065 |
| | 100 | 200 | | | -287 | 6.47 | 79/0.033 | 78/0.065 |
| 013 | 101 | | | | -286 | 6.55 | 72/0.033 | 76/0.065 |
| | 102 | | | | -286 | 6.21 | 77/0.033 | 70/0.065 |
| | 174 | | | | -286 | 6.33 | 84/0.033 | 78/0.065 |
| | 175 | 300 | | | -286 | 6.35 | 83/0.033 | 78/0.065 |
| 014 | 176 | | | | -287 | 6.02 | 72/0.033 | 73/0.065 |
| | 177 | | | | -287 | 6.16 | 71/0.033 | 71/0.065 |
| | 249 | | | | -287 | 6.37 | 79/0.033 | 78/0.065 |
| | 250 | 300 | | | -287 | 6.38 | 83/0.033 | 78/0.065 |

*Instrumentation problem - No data

TABLE VI (cont.)

| Test No. (1334-D01-OV-XXX) | Duration sec | Tank Pressure- N/m ² , g | Actuation Pressure- N/m ² , g | Inlet Temperature °K | Flow Kg/sec | Opening Time-MS Orifice-Meters | Closing Time-MS Orifice-Meters | |
|----------------------------|-----------------|---|--|----------------------------|----------------|-----------------------------------|-----------------------------------|-----------------------------|
| Pre-test functional | - | 1.72 x 10 ⁵ | 1.72 x 10 ⁶ | ambient | - | 230/7.62 x 10 ⁻⁴ | 270/1.14 x 10 ⁻³ | |
| Pre-test functional | - | 6.89 x 10 ⁵ | 1.72 x 10 ⁶ | ambient | - | 160/7.62 x 10 ⁻⁴ | 290/1.14 x 10 ⁻³ | |
| Pre-test functional | - | 1.72 x 10 ⁶ | 1.72 x 10 ⁶ | ambient | - | 120/7.62 x 10 ⁻⁴ | 270/1.14 x 10 ⁻³ | |
| Pre-test functional | - | 1.72 x 10 ⁶ | 2.41 x 10 ⁶ | ambient | - | 85/7.62 x 10 ⁻⁴ | 270/1.14 x 10 ⁻³ | |
| Test No. | Cycle No. | | | | | | | |
| 004 | 1 | 113 | 1.93 x 10 ⁵ | 1.72 x 10 ⁶ | 97.6 | 1.13 | 90/7.62 x 10 ⁻⁴ | 170/1.14 x 10 ⁻³ |
| 006 | 2 | 20 | 2.07 x 10 ⁵ | | 99.8 | * | 85/7.62 x 10 ⁻⁴ | 170/1.14 x 10 ⁻³ |
| 009 | 4 | | 2.14 x 10 ⁵ | | 98.1 | 1.20 | 105/7.62 x 10 ⁻⁴ | 185/1.14 x 10 ⁻³ |
| | 10 | 160 | 2.00 x 10 ⁵ | | 94.3 | 1.38 | 102/7.62 x 10 ⁻⁴ | 180/1.14 x 10 ⁻³ |
| 011 | 11 | | 6.89 x 10 ⁵ | | 97.0 | 2.68 | 80/8.38 x 10 ⁻⁴ | 70/1.65 x 10 ⁻³ |
| | 49 | | | | 97.0 | 2.82 | 75/8.38 x 10 ⁻⁴ | 72/1.65 x 10 ⁻³ |
| | 50 | 160 | | | 97.0 | 2.81 | 75/8.38 x 10 ⁻⁴ | 74/1.65 x 10 ⁻³ |
| 012 | 51 | | | | 95.9 | 2.74 | 75/8.38 x 10 ⁻⁴ | 70/1.65 x 10 ⁻³ |
| | 52 | | | | 95.9 | 2.80 | 77/8.38 x 10 ⁻⁴ | 70/1.65 x 10 ⁻³ |
| | 99 | | | | 95.9 | 2.82 | 80/8.38 x 10 ⁻⁴ | 75/1.65 x 10 ⁻³ |
| | 100 | 200 | | | 95.9 | 2.82 | 79/8.38 x 10 ⁻⁴ | 78/1.65 x 10 ⁻³ |
| 013 | 101 | | | | 96.5 | 2.86 | 72/8.38 x 10 ⁻⁴ | 76/1.65 x 10 ⁻³ |
| | 102 | | | | 96.5 | 2.71 | 77/8.38 x 10 ⁻⁴ | 70/1.65 x 10 ⁻³ |
| | 174 | | | | 96.5 | 2.76 | 84/8.38 x 10 ⁻⁴ | 78/1.65 x 10 ⁻³ |
| | 175 | 300 | | | 96.5 | 2.77 | 83/8.38 x 10 ⁻⁴ | 78/1.65 x 10 ⁻³ |
| 014 | 176 | | | | 95.9 | 2.62 | 72/8.38 x 10 ⁻⁴ | 73/1.65 x 10 ⁻³ |
| | 177 | | | | 95.9 | 2.69 | 71/8.38 x 10 ⁻⁴ | 71/1.65 x 10 ⁻³ |
| | 249 | | | | 95.9 | 2.78 | 79/8.38 x 10 ⁻⁴ | 78/1.65 x 10 ⁻³ |
| | 250 | 300 | | | 95.9 | 2.78 | 83/8.38 x 10 ⁻⁴ | 78/1.65 x 10 ⁻³ |

*Instrumentation problem - No data

TABLE VII. - FLUORINE CYCLE TEST RESULTS - SSOV S/N 0000002 (GOLD-PLATED CRES 304L SEAL)

| Test No. (1334-D01-OV-XXX) | Duration sec | Tank Pressure- psig | Actuation Pressure-psig | Inlet Temperature °F | Flow lb/sec | Opening Time-MS Orifice-inches | Closing Time-MS Orifice-inches | |
|----------------------------|-----------------|---------------------------|----------------------------|----------------------------|----------------|-----------------------------------|-----------------------------------|-----------|
| Pre-test functional | - | 25 He | 250 | ambient | - | 200/0.030 | 415/0.045 | |
| Pre-test functional | - | 100 He | 250 | ambient | - | 170/0.030 | 420/0.045 | |
| Pre-test functional | - | 250 He | 250 | ambient | - | 120/0.030 | 420/0.045 | |
| Pre-test functional | - | 250 He | 350 | ambient | - | 90/0.030 | 420/0.045 | |
| Test No. | Cycle No. | | | | | | | |
| 002 | 1 | 122 | 29 LF ₂ | 250 | -284 | 2.88 | 90/0.030 | 200/0.045 |
| 005 | 2 | 34 | 26 LF ₂ | 250 | -282 | * | 85/0.030 | 170/0.045 |
| 007 | 3 | | 31 LF ₂ | 250 | -279 | 2.83 | 120/0.030 | 270/0.045 |
| | 10 | 160 | 28 LF ₂ | 250 | -288 | 3.09 | 105/0.030 | 240/0.045 |
| 010 | 11 | 7 | 100 LF ₂ | 250 | -280 | 5.74 | 53/0.033 | 105/0.060 |
| 011 | 12 | | | | -280 | 4.26 | 70/0.030 | 86/0.063 |
| | 13 | | | | -280 | 4.40 | 70/0.030 | 82/0.063 |
| | 49 | | | | -280 | 6.79 | 75/0.030 | 87/0.063 |
| | 50 | 156 | | | -280 | 6.75 | 75/0.030 | 86/0.063 |
| 012 | 51 | | | | -291 | 5.83 | 67/0.030 | 70/0.067 |
| | 52 | | | | -291 | 5.95 | 63/0.030 | 70/0.067 |
| | 99 | | | | -291 | 6.22 | 71/0.030 | 77/0.067 |
| | 100 | 200 | | | -291 | 6.21 | 68/0.030 | 77/0.067 |
| 013 | 101 | | | | -286 | 6.32 | 67/0.030 | 72/0.067 |
| | 102 | | | | -286 | 6.46 | 68/0.030 | 70/0.067 |
| | 174 | | | | -286 | 6.61 | 73/0.030 | 76/0.067 |
| | 175 | 300 | | | -286 | 6.64 | 74/0.030 | 78/0.067 |
| 014 | 176 | | | | -287 | 6.62 | 62/0.030 | 71/0.067 |
| | 177 | | | | -287 | 6.67 | 62/0.030 | 70/0.067 |
| | 249 | | | | -287 | 6.46 | 73/0.030 | 75/0.067 |
| | 250 | | | | -287 | 6.44 | 69/0.030 | 73/0.067 |

*Instrumentation problem - No data.

TABLE VII (cont.)

| Test No. (1334-D01-OV-XXX) | | Duration sec | Tank Pressure- psig | Actuation Pressure-psig | Inlet Temperature °F | Flow lb/sec | Opening Time-MS Orifice-inches | Closing Time-MS Orifice-inches |
|----------------------------|-----------|-----------------|---------------------------|----------------------------|----------------------------|----------------|-----------------------------------|-----------------------------------|
| Test No. | Cycle No. | | | | | | | |
| 015 | 251 | | 250 | 250 | -279 | * | 102/0.030 | 152/0.045 |
| | 252 | | | | -279 | 14.1 | 102/0.030 | 148/0.045 |
| | 299 | | | | -281 | 14.4 | 105/0.030 | 160/0.045 |
| | 300 | 88 | | | -281 | * | 105/0.030 | 160/0.045 |
| 016 | 301 | 165 | | | -279 | 11.8 | 102/0.030 | 196**/0.045 |
| | 302 | | | | -279 | 14.2 | 109/0.030 | 137/0.045 |
| | 303 | | | | -279 | 14.1 | 103/0.030 | 141/0.045 |
| | 399 | | | | -281 | 15.5 | 120/0.030 | 152/0.045 |
| | 400 | 234 | | | -281 | 15.6 | 120/0.030 | 147/0.045 |
| | | | | | | | | |
| 017 | 401 | | | | -279 | 14.1 | 117/0.030 | 152/0.045 |
| | 402 | | | | -279 | * | 115/0.030 | 150/0.045 |
| | 599 | | | | -282 | 15.8 | 117/0.030 | 152/0.045 |
| | 600 | 160 | | | -282 | 15.7 | 115/0.030 | 150/0.045 |
| 018 | 601 | | | | -279 | 13.0 | 110/0.030 | 144/0.045 |
| | 602 | | | | -279 | 13.7 | 109/0.030 | 143/0.045 |
| | 799 | | | | -282 | 15.0 | 114/0.030 | 151/0.045 |
| | 800 | 160 | | | -282 | 14.8 | 116/0.030 | 152/0.045 |
| 019 | 801 | | | | -279 | 12.6 | 100/0.030 | 136/0.045 |
| | 802 | | | | -279 | 11.9 | 96/0.030 | 136/0.045 |
| | 999 | | | | -282 | 13.4 | 110/0.030 | 157/0.045 |
| | 1000 | | | | -282 | 13.5 | 113/0.030 | 156/0.045 |
| 019 | 1001 | | | | -282 | * | 110/0.030 | 60/0.067 |
| | 1002 | | | | -282 | 17.6 | 102/0.030 | 58/0.067 |
| | 1003 | | | | -282 | 16.7 | 102/0.030 | 58/0.067 |
| | 1004 | | | | -282 | 16.5 | 103/0.030 | 58/0.067 |
| | 1005 | | | | -282 | 16.4 | 103/0.030 | 57/0.067 |
| | 1006 | 164 | | | -282 | * | 105/0.030 | 55/0.067 |

*Instrumentation problem - No data

**Long duration flow test - not a pressure shutdown

TABLE VII (cont.)

| Test No. (1334-D01-OV-XXX) | Duration sec | Tank Pressure- N/m ² , g | Actuation Pressure- N/m ² , g | Inlet Temperature °K | Flow- Kg/sec | Opening Time-MS Orifice-meters | Closing Time-MS Orifice-meters | |
|----------------------------|-----------------|---|--|----------------------------|-----------------|-----------------------------------|-----------------------------------|-----------------------------|
| Pre-test functional | - | 1.72 x 10 ⁵ | 1.72 x 10 ⁶ | ambient | - | 200/7.62 x 10 ⁻⁴ | 415/1.14 x 10 ⁻³ | |
| Pre-test functional | - | 6.89 x 10 ⁵ | 1.72 x 10 ⁶ | ambient | - | 170/7.62 x 10 ⁻⁴ | 420/1.14 x 10 ⁻³ | |
| Pre-test functional | - | 1.72 x 10 ⁶ | 1.72 x 10 ⁶ | ambient | - | 120/7.62 x 10 ⁻⁴ | 420/1.14 x 10 ⁻³ | |
| Pre-test functional | - | 1.72 x 10 ⁶ | 2.41 x 10 ⁶ | ambient | - | 90/7.62 x 10 ⁻⁴ | 420/1.14 x 10 ⁻³ | |
| Test No. | Cycle No. | | | | | | | |
| 002 | 1 | 122 | 2.00 x 10 ⁵ | 1.72 x 10 ⁶ | 97.6 | 1.31 | 90/7.62 x 10 ⁻⁴ | 200/1.14 x 10 ⁻³ |
| 005 | 2 | 34 | 1.79 x 10 ⁵ | | 98.7 | * | 85/7.62 x 10 ⁻⁴ | 170/1.14 x 10 ⁻³ |
| 007 | 3 | | 2.14 x 10 ⁵ | | 100.4 | 1.28 | 120/7.62 x 10 ⁻⁴ | 270/1.14 x 10 ⁻³ |
| | 10 | 160 | 1.93 x 10 ⁵ | | 95.4 | 1.40 | 105/7.62 x 10 ⁻⁴ | 240/1.14 x 10 ⁻³ |
| 010 | 11 | 7 | 6.89 x 10 ⁵ | | 99.8 | 2.60 | 53/8.37 x 10 ⁻⁴ | 105/1.52 x 10 ⁻³ |
| 011 | 12 | | | | | 1.93 | 70/7.62 x 10 ⁻⁴ | 86/1.60 x 10 ⁻³ |
| | 13 | | | | | 1.99 | 70/7.62 x 10 ⁻⁴ | 82/1.60 x 10 ⁻³ |
| | 49 | | | | | 3.08 | 75/7.62 x 10 ⁻⁴ | 87/1.60 x 10 ⁻³ |
| | 50 | 156 | | | | 3.06 | 75/7.62 x 10 ⁻⁴ | 86/1.60 x 10 ⁻³ |
| 012 | 51 | | | | 93.7 | 2.64 | 67/7.62 x 10 ⁻⁴ | 70/1.70 x 10 ⁻³ |
| | 52 | | | | | 2.70 | 63/7.62 x 10 ⁻⁴ | 70/1.70 x 10 ⁻³ |
| | 99 | | | | | 2.82 | 71/7.62 x 10 ⁻⁴ | 77/1.70 x 10 ⁻³ |
| | 100 | 200 | | | | 2.82 | 68/7.62 x 10 ⁻⁴ | 77/1.70 x 10 ⁻³ |
| 013 | 101 | | | | 96.5 | 2.86 | 67/7.62 x 10 ⁻⁴ | 72/1.70 x 10 ⁻³ |
| | 102 | | | | | 2.93 | 68/7.62 x 10 ⁻⁴ | 70/1.70 x 10 ⁻³ |
| | 174 | | | | | 3.00 | 73/7.62 x 10 ⁻⁴ | 76/1.70 x 10 ⁻³ |
| | 175 | 300 | | | | 3.01 | 74/7.62 x 10 ⁻⁴ | 78/1.70 x 10 ⁻³ |
| 014 | 176 | | | | 95.9 | 3.00 | 62/7.62 x 10 ⁻⁴ | 71/1.70 x 10 ⁻³ |
| | 177 | | | | | 3.02 | 62/7.62 x 10 ⁻⁴ | 70/1.70 x 10 ⁻³ |
| | 249 | | | | | 2.93 | 73/7.62 x 10 ⁻⁴ | 75/1.70 x 10 ⁻³ |
| | 250 | 300 | | | | 2.92 | 69/7.62 x 10 ⁻⁴ | 73/1.70 x 10 ⁻³ |

*Instrumentation problem - No data

TABLE VII (cont.)

| Test No. (1334-D01-OV-XXX) | Duration sec | Tank Pressure- N/m ² , g | Actuation Pressure- N/m ² , g | Inlet Temperature °K | Flow Kg/sec | Opening Time-MS Orifice-meters | Closing Time-MS Orifice-meters |
|----------------------------|-----------------|---|--|----------------------------|----------------|-----------------------------------|-----------------------------------|
| Test No. | Cycle No. | | | | | | |
| 015 | 251 | 1.72 x 10 ⁶ | 1.72 x 10 ⁶ | 100.4 | * | 102/7.62 x 10 ⁻⁴ | 152/1.14 x 10 ⁻³ |
| | 252 | | | 100.4 | 6.40 | 102/7.62 x 10 ⁻⁴ | 148/1.14 x 10 ⁻³ |
| | 299 | | | 99.3 | 6.53 | 105/7.62 x 10 ⁻⁴ | 160/1.14 x 10 ⁻³ |
| | 300 | | | 99.3 | * | 105/7.62 x 10 ⁻⁴ | 160/1.14 x 10 ⁻³ |
| 016 | 301 | 165 | | 100.4 | 5.35 | 102/7.62 x 10 ⁻⁴ | 196**/1.14 x 10 ⁻³ |
| | 302 | | | 100.4 | 6.44 | 109/7.62 x 10 ⁻⁴ | 137/1.14 x 10 ⁻³ |
| | 303 | | | 100.4 | 6.40 | 103/7.62 x 10 ⁻⁴ | 141/1.14 x 10 ⁻³ |
| | 399 | | | 99.3 | 7.03 | 120/7.62 x 10 ⁻⁴ | 152/1.14 x 10 ⁻³ |
| | 400 | 234 | | 99.3 | 7.07 | 120/7.62 x 10 ⁻⁴ | 147/1.14 x 10 ⁻³ |
| 017 | 401 | | | 100.4 | 6.40 | 117/7.62 x 10 ⁻⁴ | 152/1.14 x 10 ⁻³ |
| | 402 | | | 100.4 | * | 115/7.62 x 10 ⁻⁴ | 150/1.14 x 10 ⁻³ |
| | 599 | | | 98.7 | 7.16 | 117/7.62 x 10 ⁻⁴ | 152/1.14 x 10 ⁻³ |
| | 600 | 160 | | 98.7 | 7.12 | 115/7.62 x 10 ⁻⁴ | 150/1.14 x 10 ⁻³ |
| 018 | 601 | | | 100.4 | 5.89 | 110/7.62 x 10 ⁻⁴ | 144/1.14 x 10 ⁻³ |
| | 602 | | | 100.4 | 6.21 | 109/7.62 x 10 ⁻⁴ | 143/1.14 x 10 ⁻³ |
| | 799 | | | 98.7 | 6.80 | 114/7.62 x 10 ⁻⁴ | 151/1.14 x 10 ⁻³ |
| | 800 | 160 | | 98.7 | 6.66 | 116/7.62 x 10 ⁻⁴ | 152/1.14 x 10 ⁻³ |
| 019 | 801 | | | 100.4 | 5.71 | 100/7.62 x 10 ⁻⁴ | 136/1.14 x 10 ⁻³ |
| | 802 | | | 100.4 | 5.40 | 96/7.62 x 10 ⁻⁴ | 136/1.14 x 10 ⁻³ |
| | 999 | | | 98.7 | 6.07 | 110/7.62 x 10 ⁻⁴ | 157/1.14 x 10 ⁻³ |
| | 1000 | | | 98.7 | 6.12 | 113/7.62 x 10 ⁻⁴ | 156/1.14 x 10 ⁻³ |
| 019 | 1001 | | | 98.7 | * | 110/7.62 x 10 ⁻⁴ | 60/1.70 x 10 ⁻³ |
| | 1002 | | | | 7.98 | 102/7.62 x 10 ⁻⁴ | 58/1.70 x 10 ⁻³ |
| | 1003 | | | | 7.57 | 102/7.62 x 10 ⁻⁴ | 58/1.70 x 10 ⁻³ |
| | 1004 | | | | 7.48 | 103/7.62 x 10 ⁻⁴ | 58/1.70 x 10 ⁻³ |
| | 1005 | | | | 7.44 | 103/7.62 x 10 ⁻⁴ | 57/1.70 x 10 ⁻³ |
| | 1006 | | | | * | 105/7.62 x 10 ⁻⁴ | 55/1.70 x 10 ⁻³ |

*Instrumentation problem - No data

**Long duration flow test - not a pressure shutdown

TABLE VIII. - LEAKAGE TEST RESULTS - SSOV S/N 0000001 (BERYLLIUM NICKEL SEAL)

| Test | Temperature | Leakage (SCCS) at Test Pressure (psig) | | |
|---------------------|-----------------|--|---|---|
| | | 25 (1.72 x 10 ⁵ N/m ² , g | 100 (6.89 x 10 ⁵ N/m ² , g | 250 (1.72 x 10 ⁶ N/m ² , g |
| Acceptance test | ambient | 9.10 x 10 ⁻⁴ | 2.20 x 10 ⁻³ | 2.66 x 10 ⁻³ |
| Acceptance test | LN ₂ | - | - | 3.40 x 10 ⁻³ |
| Post facility inst. | ambient | 1.0 x 10 ⁻² | 2.66 x 10 ⁻² | 8.66 x 10 ⁻² |
| Post facility inst. | LN ₂ | 0 ^{cc} /5 min | 6.33 x 10 ⁻² | 6.60 x 10 ⁻¹ |
| Post-passivation | LN ₂ | 1.36 x 10 ⁻¹ | 7.75 x 10 ⁻¹ | 2.63 |
| Post-Cycle 1 | LN ₂ | 2.13 x 10 ⁻¹ | 1.28 | 4.35 |
| Post-Cycle 2 | LN ₂ | 6.66 x 10 ⁻¹ | 1.85 | 4.75 |
| Post-Cycle 10 | LN ₂ | 2.26 x 10 ⁻¹ | 1.49 | 5.00 |
| Post-Cycle 50 | ambient | 5.67 x 10 ⁻² | 2.20 x 10 ⁻¹ | 8.12 x 10 ⁻¹ |
| Post-Cycle 100 | ambient | 3.33 x 10 ⁻² | 1.60 x 10 ⁻¹ | 5.95 x 10 ⁻¹ |
| Post-Cycle 175 | ambient | 3.33 x 10 ⁻² | 1.53 x 10 ⁻¹ | 5.55 x 10 ⁻¹ |
| Post-Cycle 250 | LN ₂ | 1.20 x 10 ⁻¹ | 7.52 x 10 ⁻¹ | 2.44 |
| Acceptance test | ambient | 1.12 x 10 ⁻¹ | 2.50 x 10 ⁻¹ | 6.83 x 10 ⁻¹ |

Note: Design goal was 2.50 x 10⁻² SCCS maximum.

TABLE IX. - LEAKAGE TEST RESULTS - SSOV S/N 0000002 (GOLD-PLATED CRES 304L SEAL)

| Test | Temperature | Leakage (SCCS) at Test Pressure (psig) | | |
|---------------------|-----------------|---|--|--|
| | | 25 (1.72×10^5 N/m ² , g | 100 (6.89×10^5 N/m ² , g | 250 (1.72×10^6 N/m ² , g |
| Acceptance test | ambient | - | 5.20×10^{-3} | 1.70×10^{-3} |
| Acceptance test | LN ₂ | - | - | 1.50×10^{-1} |
| Post facility inst. | ambient | 0 ^{cc} /5 min | 0 ^{cc} /5 min | 5.00×10^{-3} |
| Post facility inst. | LN ₂ | 0 ^{cc} /5 min | 0 ^{cc} /5 min | 6.66×10^{-3} |
| Post-passivation | LN ₂ | 0 ^{cc} /5 min | 0 ^{cc} /5 min | 4.00×10^{-2} |
| Post-Cycle 1 | LN ₂ | 0 ^{cc} /5 min | 0 ^{cc} /5 min | 1.33×10^{-2} |
| Post-Cycle 2 | LN ₂ | 0 ^{cc} /5 min | 0 ^{cc} /5 min | 2.66×10^{-2} |
| Post-Cycle 10 | LN ₂ | 0 ^{cc} /5 min | 0 ^{cc} /5 min | 5.55×10^{-3} |
| Post-Cycle 50 | ambient | 8.33×10^{-4} | 1.67×10^{-3} | 3.33×10^{-3} |
| Post-Cycle 100 | ambient | 0 ^{cc} /5 min | 1.67×10^{-3} | 2.00×10^{-2} |
| Post-Cycle 175 | ambient | 1.67×10^{-3} | 3.33×10^{-3} | 1.67×10^{-2} |
| Post-Cycle 250 | LN ₂ | 3.33×10^{-3} | 3.66×10^{-2} | 1.27×10^{-1} |
| Post-Cycle 300 | ambient | 8.33×10^{-4} | 3.33×10^{-3} | 6.67×10^{-3} |
| Post-Cycle 400 | LN ₂ | 0 ^{cc} /5 min | 1.66×10^{-2} | 3.66×10^{-2} |
| Post-Cycle 600 | LN ₂ | * | * | * |
| Post-Cycle 800 | ambient | 2.50×10^{-3} | 2.33×10^{-2} | 7.33×10^{-2} |
| Post-Cycle 1006 | LN ₂ | 1.66×10^{-3} | 3.66×10^{-2} | 1.00×10^{-1} |
| Acceptance test | ambient | 5.33×10^{-3} | 2.05×10^{-2} | 5.66×10^{-2} |
| Acceptance test | LN ₂ | 2.08×10^{-2} | 1.66×10^{-1} | 6.33×10^{-1} |

*Invalid results because of a leak in the system.

**Equivalent liquid fluorine leakage = 7.95×10^{-6} PPS (3.61×10^{-6} Kg/sec) LF₂Note: Design goal was 2.50×10^{-2} SCCS maximum.

within the design goal of 2.50×10^{-2} SCCS at 250 psig ($1.72 \times 10^6 \text{ N/m}^2$, g) helium pressure for 175 liquid fluorine cycles. This leakage increased to 1.00×10^{-1} SCCS after 1006 cycles. Valve pressure drop at rated flow was 3.3 psid ($2.27 \times 10^4 \text{ N/m}^2$).

The test potentiometers attached to the valve actuator pistons and mounted on the actuator end of the valves were used as the primary instrumentation to measure valve travel times. The proximator probes also were monitored but a comparison of the two probe outputs always gave a longer valve travel time than the potentiometer. During valve travel, the probe from which the washer was moving would signal valve movement within 5 milliseconds from the initial potentiometer signal. However, the probe to which the washer was moving would not signal that valve movement was complete until 75 to 80 milliseconds after the potentiometer signal. This occurred in either the opening or closing direction. After a discussion with the probe supplier, it was determined that the delay was caused by the circuit in the proximator which drove the probe. Proximitors with shorter delay times were available on special order, but all cycles were conducted with the proximitors on hand.

3. Valve Disassembly and Inspection

The valves were subjected to acceptance leakage tests in the Engineering Laboratories and then disassembled. There was no change in valve stroke or actuator spring load in either assembly. Both actuators and bellows were in good condition.

The spherical surface of the beryllium nickel seal had a cloudy appearance. Seal standoff remained unchanged from that set during assembly. Some of the beryllium nickel material had transferred to the electrolized Inconel 718 seat. A view of the seat is shown on Figure 12.

The gold-plated CRES 304L seal and seat were in good condition although the gold had a dull, cloudy appearance. Seal standoff, however, had changed to 0.00092-in. ($2.337 \times 10^{-5} \text{ m}$), a decrease of 48% from the 0.00177-in. ($4.496 \times 10^{-5} \text{ m}$) setting made and checked during assembly. The gold plate was in good condition and there was no evidence that it had been distorted by contact with the seat. Figure 13 is a view of the two seals after they were removed from the valves.

The copper Conoseals used to seal the inlet and outlet flanges were in good condition and performed with zero leakage through the test.

IV. DISCUSSION OF RESULTS

All of the liquid flow cycles were performed successfully without any problem or damage to the two space storable oxidizer valves. The materials selected for the valves also performed satisfactorily during passivation and the fluorine flow tests without any evidence of fluorine reaction. Even the

NOT REPRODUCIBLE




Figure 12. View of the Electrolized Inconel 718 Seat from
SSOV S/N 0000001 after Fluorine Exposure




Figure 13. View of the Metal Seals after Fluorine Exposure

threads and the locking strips, which are normally considered vulnerable when exposed in the flow stream, displayed no damage. This performance verified that the proper valve material was selected, the space storable oxidizer valves were properly cleaned and assembled, and that the flow system was assembled and maintained in a scrupulously clean condition.

The valve pressure drop of 3.3 psid ($2.27 \times 10^4 \text{ N/m}^2$) at design flow rate was well within the design goal of 5.0 psid ($3.45 \times 10^4 \text{ N/m}^2$). Valve actuation times were easily controlled by orificing the actuator helium supply and vent lines. The valve bellows, actuators, and the proximator probes performed satisfactorily throughout the program. They were in good condition when inspected during the post-test valve disassembly operation.

The transfer of beryllium nickel material to the valve seat definitely caused the leakage measured for the beryllium nickel seal. This phenomenon had occurred once before with another beryllium nickel seal in an SSOV. It is believed that diffusion bonding occurs between the beryllium nickel seal and the seat. This is caused by localized deformation of the high points in the sealing surface where the yield strength of the beryllium nickel is exceeded. Microscopic bits of material then are pulled from the seal surface when the valve is actuated. This occurred after the newly assembled and acceptance tested valve remained inactive in the closed position for a period of two weeks in both instances.

A beryllium nickel seal was successfully used in a bipropellant valve⁽⁶⁾ designed for use with oxygen difluoride (OF_2) and diborane (B_2H_6) without material transfer. Spherical poppet seals, smaller but similar to the one used in the SSOV, were installed in 20-degree conical seats. The seat material and plating were the same as that used in the SSOV. This valve has a higher seal loading than the SSOV but there was no material transfer even after inactive periods in excess of three weeks. The difference in performance between the two seals could result from the different seat angles. Additional analysis and testing are required to completely evaluate the material transfer problem and the use of unplated beryllium nickel as an SSOV seal material.

Sealing of the SSOV main shutoff seal is dependent upon the seal load against the seat. This load is controlled by the adjustment of the seal stand-off setting made between the seal and stop as previously discussed. Both the beryllium nickel seal and the CRES 304L seal were subjected to a thermal stabilization cycle during manufacture to prevent changes in this setting resulting from material changes during use. The seals were rough machined, then subjected to ten thermal cycles from room temperature to -320°F (77.6°K), and back to room temperature prior to finish machining. This process was intended to remove all internal stresses in the material so that the material would be stable after machining and would not be affected by cryogenic cycling in the valve.

(6) Bipropellant Shutoff Valve, Aerojet Liquid Rocket Company Interim Report 7-733-II, Contract NAS 7-733, 15 December 1970.

Apparently the beryllium nickel material was stabilized by the thermal cycling while the CRES 304L was not. A more effective, but more hazardous, thermal stabilization of the low 300 series stainless steels would be to utilize a liquid hydrogen soak at -423°F (20.4°K). It can be postulated that some phase transformation occurred in the CRES 304L (i.e., austenite changing to martensite) when the material was subjected to cryogenic temperatures during test, or that there was creep in the CRES 304L material when the seal was under load.

V. CONCLUSIONS

The CRES 304L material does not appear to have the stability required for this type of metal seal. The loss of seal standoff because of a change in material detracted from an otherwise excellent valve performance. Also, the transfer of the beryllium nickel material to the valve seat was an unexpected anomaly. The beryllium nickel seal performed satisfactorily in all other respects and there was no change in seal standoff. The gold plate on the CRES 304L seal prevented galling throughout the 1006 test cycles and was in good condition at the end of testing.

It can be concluded that a gold-plated beryllium nickel seal would give excellent service in a fluorine valve. The beryllium nickel would maintain the set standoff adjustment and the gold plate would prevent transfer of the beryllium nickel material. Both materials were proven to be compatible with fluorine for long exposure periods. The materials are readily available and no manufacturing problems are anticipated.

VI. RECOMMENDATIONS

It is recommended that a gold-plated beryllium nickel seal be evaluated in one of the test valves. The hardware is available and the beryllium nickel seals can be repolished and plated at nominal cost. The procedures and techniques for assembly and testing are developed and refined as a result of the program completed. This assures an effective follow-on program at minimal costs and time. The recommended evaluation would complement the SSOV program and would provide necessary data regarding fluorine technology.

Additional analysis and testing are required to ascertain why the beryllium nickel seal material transferred to the valve seat. This material performed satisfactorily in all other respects and its compatibility in a fluorine environment was demonstrated. It is recommended that a material evaluation be performed to ascertain the reason for the phenomenon which will allow extended use of this relatively new material.

APPENDIX A
COMPATIBILITY TEST PLAN

PRECEDING PAGE BLANK NOT FILMED

17 September 1970

Revision 1

COMPATABILITY TEST PLAN

SPACE STORABLE OXIDIZER VALVE PROGRAM

CONTRACT: NAS 3-12035

TITLE:


FLUORINE COMPATABILITY TESTING
OF THE SPACE STORABLE OXIDIZER
VALVE


Prepared for . .

NASA Lewis Research Center
Cleveland, Ohio

by

Liquid Rocket Division
Aerojet-General Corporation
Sacramento, California

Approved By: 
O D Goodman
Program Manager

Prepared by: 
R L Crosier
Project Engineer

PRECEDING PAGE BLANK NOT FILMED

Revisions

Number

Pages

Date

1

Enclosures (1) and (2)

9-17-70

PRECEDING PAGE BLANK NOT FILMED

| | <u>TABLE OF CONTENTS</u> | <u>PAGE</u> |
|------|---|-------------|
| I. | <u>NAME AND FUNCTION OF COMPONENT</u> | 49 |
| II. | <u>PURPOSE OF TESTS</u> | 49 |
| III. | <u>REQUIREMENTS</u> | 49 |
| | A. DOCUMENTATION | 49 |
| | B. INSTRUMENTATION | 52 |
| | C. TEST FACILITIES | 54 |
| | D. ACCEPTABLE CRITERIA | 55 |
| IV. | <u>TEST PROCEDURES</u> | 55 |
| | A. PRE-TEST OPERATIONS | 55 |
| | B. PASSIVATION PROCEDURE | 56 |
| | C. PRE-TEST FUNCTIONAL AND LEAKAGE TESTS | 57 |
| | D. LIFE CYCLE TESTING AT INLET PRESSURES OF 25 and 100 PSIG | 59 |
| | E. LIFE CYCLE TESTING AT INLET PRESSURE OF 250 PSIG | 59 |
| | F. POST-TEST FUNCTIONAL AND LEAKAGE TESTS | 60 |

FIGURES

| | | |
|----|---|----|
| 14 | Cross Sectional View of Space Storable Oxidizer Valve | 50 |
| 15 | Test Setup Schematic | 51 |

Enclosures:

| | | |
|-----|---|----|
| (1) | Test Parameters for Tests Conducted at Inlet Pressures of 25 and 100 psig | 61 |
| (2) | Test Parameters for Tests Conducted at Inlet Pressures of 250 psig | 62 |

TABLES

| | | |
|---|----------------------|----|
| X | Test Instrumentation | 53 |
|---|----------------------|----|

I. NAME AND FUNCTION OF COMPONENT

The component to be tested is the Space Storable Oxidizer Valve (SSOV), P/N 1157220, designed and fabricated under NASA Contract No. NAS 3-12035. The function of the component is to provide an on-off oxidizer flow control for use on rocket engines using LF_2 , LO_2 and FLOX as an oxidizer. Figure 14 shows a cross sectional view of the valve, and Figure 15 the test setup schematic.

II. PURPOSE OF TESTS

The purpose of this test program is to demonstrate that the Aerojet-General designed SSOV will function properly in a gaseous and liquid fluorine environment. Compatability of materials with fluorine, cycle endurance, and the capability of the main shut-off seal to satisfy the low leakage criteria specified in the governing contract will be demonstrated. Two valves will be tested; one valve will utilize a gold-plated CRES 304L shut-off seal and the second valve will use a beryllium nickel seal. The two configurations will be P/N 1157220-9 and P/N 1157220-19, respectively.

III. REQUIREMENTS

A. DOCUMENTATION

1. The part number, serial number, and description of the valve assembly tested will be listed with the test data.
2. An accurate chronological history of all significant events that occur during testing will be maintained for the test. This record will contain the test title, date, time, number, and validity, a brief description and explanation of each discrepancy, and any other documentation or information pertinent to the test.
3. All original data records (such as oscillograph paper and




Figure 14. Cross Sectional View of Space Storable Oxidizer Valve




Figure 15. Test Setup Schematic

III,A,3, (continued)

strip charts) will be labeled to fully identify the test and all recorded parameters.

4. A record of cumulative total valve cycles and cumulative valve exposure time to fluorine will be maintained for each test.

5. Still black and white photographs will be taken of the test setup and of any significant hardware failure or damage incurred during the performance of the tests.

6. Check lists will be prepared and utilized to ensure that each testing sequence is performed in conformance with the requirements of this document. The completion of each step will be verified by the initials or stamp of the individual performing the task.

7. A Test Request form will be issued by the project engineer to initiate test facility preparation and testing. Test Request Supplements will be issued for each test change or investigation conducted on an SSOV assembly or component.

8. Additional records and forms may be inaugurated as the need arises; however, the need and format of these records must be approved by the cognizant project engineer prior to their use.

B. INSTRUMENTATION

1. The calibration of equipment and instrumentation specified herein will be in accordance with the requirements of Specification MIL-C-45662, Calibration System Requirements, and the AGC Sacramento Liquid Rocket Plant Measurement Standards Instructions Manual.

2. Instrumentation for this test series will be as specified in Table X. Any additional instrumentation required for performance of the tests is left to the discretion of the test facility personnel.

TABLE X
TEST INSTRUMENTATION

| <u>Parameter</u> | <u>Transducer</u> | <u>Recorder</u> | <u>Range</u> | <u>Response</u> |
|-----------------------------------|-------------------|-----------------------------|------------------|-----------------|
| Inlet Pressure | Strain Gage | Strip Chart or Oscillograph | 0-500 psig | 0-500 cps |
| Outlet Pressure | " | " | " | 0-100 cps |
| Spring Cavity Pressure | " | " | 0-100 psig | " |
| Actuation Inlet Pressure | " | " | 0-1000 psig | " |
| Closed Proximitors Output Voltage | Direct | " | 0-30 Vdc | 0-500 cps |
| Open Proximitors Output Voltage | " | " | " | " |
| Potentiometer | " | " | 0-5 Vdc | " |
| Pilot Valve Current | " | " | 0-2 amps | " |
| Propellant Inlet Temperature | Thermocouple | " | +100 to -320°F | 0-5 cps |
| Valve Outlet Flange Temperature | " | " | " | " |
| Temperature Near Open Proximitors | " | " | " | " |
| Propellant Flow | Flowmeter | " | 0-15 lb/sec | - |
| Fire Switch | Direct | " | 0-30 Vdc | 0-100 cps |
| Shutoff Seal Leak Pressure | Strain Gage | " | 0-5 or 0-10 psig | " |
| Bellows Leak Pressure | " | " | " | " |

Total steady state measurement accuracy (3 σ) will be $\pm 2\%$.

III,B, (continued)

3. Instrumentation locations and connections will be as required to obtain optimum measurement accuracy and to minimize errors due to such factors as lead wire impedance and sensing line pressure drop.

4. As a minimum, the following parameters will be measured:

| | | |
|-----|-----------------------------------|-----|
| (a) | Valve inlet pressure | Pi |
| (b) | Valve outlet pressure | Po |
| (c) | Propellant flow rate | FMo |
| (d) | Spring cavity pressure | Psc |
| (e) | Actuation inlet pressure | Pa |
| (f) | Closed proximitior output voltage | Vcp |
| (g) | Open proximitior output voltage | Vop |
| (h) | Linear potentiometer | LOV |
| (i) | Pilot valve current | Ipv |
| (j) | Fire switch | FS |
| (k) | Propellant inlet temperature | Ti |
| (l) | Valve outlet flange temperature | Tof |
| (m) | Temperature near open proximitior | Top |

C. TEST FACILITIES

1. Actuation fluid and leak test fluid will be Bureau of Mines Grade A gaseous helium with a maximum dew point of -70°F .

2. Oxidizer will be liquid fluorine with the following analysis by weight: 98.7% LF_2 minimum, 0.3% maximum HF and CH_4 , and 1.0% maximum O_2 , N_2 , and other inerts.

III,C, (continued)

3. All actuation test fluids will be filtered through 10 micron nominal, 25 micron absolute, filters immediately before entering the valve.

4. Service ports that are vented to atmosphere during testing (valve ports 5 and/or 6) will be protected by a vent check valve.

5. The internal surfaces of the valve and test system will be maintained clean to Level D or E of Specification AGC-46350 throughout all testing specified herein.

D. ACCEPTABLE CRITERIA

1. The valve opening and closing times as measured from the potentiometer trace shall be 50 to 75 milliseconds.

2. Leakage from the propellant cavity to the actuation cavity (across the bellows) shall not exceed 1×10^{-6} SCCS helium.

3. Leakage across the poppet seal shall not exceed 2.5×10^{-2} SCCS helium.

4. If the acceptable criteria is exceeded, the cognizant project engineer will be notified before additional tests are conducted.

IV. TEST PROCEDURES

A. PRE-TEST OPERATIONS

1. The valve assembly will be visually inspected for shipping damage and port covers when it is received for test.

IV,A, (continued)

2. It will be verified that the valve has passed an acceptance test and a cleanliness verification test in accordance with Specification AGC-46966 within three weeks prior to receipt of valve for test.

3. Prior to installation of the valve into the passivation system, the system will be cleaned, leak checked, and passivated with gaseous fluorine, as required, in accordance with standard test facility procedures.

B. PASSIVATION PROCEDURE

1. The valve will be installed in the passivation and flow facility by personnel wearing clean standard plastic disposable gloves to maintain the cleanliness level.

2. With the valve in the open position and port 2 capped or closed off downstream, the valve cavity will be purged with helium and then evacuated to 22 to 29 in. Hg. through ports 1 and 3.

3. Gaseous fluorine will be slowly introduced into the evacuated valve cavity through ports 1 and 3 until the system pressure reaches 5 to 10 psig. This pressure will be maintained for 15 minutes minimum. During this period, the valve will be cycled closed and open five times. The system pressure and temperature will be monitored for any indication of excessive reaction throughout the passivation period.

4. The valve will be re-evacuated, then backfilled with gaseous fluorine to a pressure of 80 to 100 psig. This pressure will be maintained for 30 minutes minimum. The valve will be cycled closed and

IV,B, (continued)

open four times during this period.

5. The system pressure will be increased to 240 to 260 psig by the addition of gaseous fluorine or gaseous helium. This pressure will be maintained for two hours minimum. During this period, the valve will be cycled closed and open two times.

6. The system will be vented to zero psig, then purged with gaseous helium for two minutes minimum. The valve will be cycled closed.

7. The passivation procedure will be repeated whenever a line is broken and/or a valve is replaced.

C. PRE-TEST FUNCTIONAL AND LEAKAGE TESTS

1. With the valve immersed in LN_2 , Tof at -300°F maximum, and the inlet port unpressurized, the outlet port will be checked for leakage. This test will determine the tare leakage of the test system and will be conducted immediately prior to all leakage tests. The test duration will be 15 minutes minimum. Tare leakage will be subtracted from the test leakage to determine the true leakage of the poppet seal during subsequent leakage tests.

2. With the valve still immersed in LN_2 and Tof at -300°F maximum, the valve inlet port will be pressurized with gaseous helium to 25^{+5}_{-0} psig. The valve will be cycled open and closed one time. Opening and closing times shall be in accordance with III.D. for all functional and endurance cycles.

3. With the 25^{+5}_{-0} psig helium pressure and -300°F maximum temperature maintained and the leakage detection system isolation valve open, a leak test will be conducted across the main shutoff seal for 15 minutes

IV,C, (continued)

minimum. All leakages will be recorded and shall not exceed the leakage rates specified in III.D. If leakage is found to be greater than the acceptable limit, the cognizant project engineer will be notified before additional tests are conducted.

4. The helium pressure at the valve inlet will be increased to 100^{+10}_{-0} psig, then the valve will be cycled open and closed.

5. The leakage test of IV.C.3 will be repeated except the inlet pressure will be 100^{+10}_{-0} psig.

6. The helium pressure at the valve inlet will be increased to 250^{+25}_{-0} psig, then the valve will be cycled open and closed.

7. The leakage test of IV.C.3 will be repeated except the inlet pressure will be 250^{+25}_{-0} psig.

8. With Tof maintained at -300°F maximum and ports 2 and 3 at zero psig pressure, port 5 will be checked for a pressure increase or decrease over a 15 minute test period. This test will determine the tare pressure change in the valve spring cavity and will be conducted immediately prior to each bellows leak test. The spring cavity pressure will be adjusted by the tare pressure change to determine the true pressure increase during the bellows leak test. This test may be conducted during the 250 psig shutoff seal leakage test.

9. With Tof maintained at -300°F maximum and ports 1,2, and 3 pressurized to 250^{+25}_{-0} psig, port 5 will be checked for a pressure increase over a 15 minute test period. No pressure increase will be allowed.

IV, (continued)

D. LIFE CYCLE TESTING AT INLET PRESSURES OF 25 AND 100 PSIG

NOTE: Two valves will be subjected to the following tests:

1. The valve will be subjected to liquid fluorine flow tests at the test conditions specified in Enclosure (1). The system will be bled and cooled prior to testing to ensure liquid flow. During flow testing, the actuator potentiometer trace and spring cavity pressure reading will be visually monitored for any indication of malfunction.

2. During flow testing, the main shutoff seal and bellows will be leak tested at the intervals shown in Enclosure (1). Leakage tests will be conducted with gaseous helium with the valve immersed in LN_2 and with Tof at $-300^{\circ}F$ maximum. Leakage tests will be conducted in accordance with the pre-test leakage tests, IV.C.1,3,5,7,8, and 9. All valve leakage will be recorded.

3. A valve cycle will consist of the following:

a. The valve will be cycled open by energizing the system pilot valve.

b. The valve will be held in the full open position until stabilized flow has been obtained.

c. The valve will be cycled closed by deenergizing the system pilot valve.

d. Valve actuation times shall be in accordance with III.D.

E. LIFE CYCLE TESTING AT INLET PRESSURE OF 250 PSIG

NOTE: The "better valve" from the preceeding test series will

IV, E, (continued)

be subjected to the following tests:

1. This series of tests will be identical to the preceeding test series (IV.D) except the valve inlet pressure will be 250 psig and leakage checks will be conducted at intervals in accordance with Enclosure (2). The valve cycle specified in IV.D.3 will be utilized for this test series.

F. POST-TEST FUNCTIONAL AND LEAKAGE TESTS

1. A post-test functional test, and post-test leakage tests of the main shutoff seal and bellows, will be conducted at room ambient temperature in accordance with Specification AGC-46966.

Space Storable Oxidizer Valve Test Parameters for Tests Conducted
at Inlet Pressures of 25 and 100 psig

Each of two valves will be subjected to 250 LF_2 endurance cycles; the first of ten cycles will be conducted with an inlet pressure of 25 psig, the remaining 240 cycles will be conducted with an inlet pressure of 100 psig.

| <u>Parameter</u> | <u>First 10 Cycles</u> | <u>Last 240 Cycles</u> |
|---|--|---|
| Test Fluid | LF_2 | LF_2 |
| Inlet Pressure (psig) | $25 \begin{smallmatrix} +5 \\ -0 \end{smallmatrix}$ | $100 \begin{smallmatrix} +10 \\ -0 \end{smallmatrix}$ |
| Flow Rate (lb/sec) | $9 \begin{smallmatrix} +1.0 \\ -0.5 \end{smallmatrix}$ | $12 \begin{smallmatrix} +1.0 \\ -0.5 \end{smallmatrix}$ |
| Maximum Pressure Drop at Rated Flow (psid) | 5 | 5 |
| Actuation Fluid | GH_e | GH_e |
| Actuation Pressure (psig) | 500 ± 15 | 500 ± 15 |
| Pilot Valve Voltage (Vdc) | 28 ± 2 | 28 ± 2 |
| Proximitator Voltage (Vdc) | -28 ± 0.1 | -28 ± 0.1 |
| Potentiometer Voltage (Vdc) | 5 ± 0.1 | 5 ± 0.1 |
| Leakage Tests at (No. Cycles) | 1,2,10 | 50,100,175,250 |
| Exposure Flow Time, Min (Sec) | 30* | 570* |

| <u>*Exposure Flow Time at Leakage Tests, Min. (Sec)</u> | <u>Cycles</u> | <u>Exposure Time</u> |
|---|---------------|----------------------|
| | 1 | 3 |
| | 2 | 6 |
| | 10 | 30 |
| | 50 | 140 |
| | 100 | 275 |
| | 175 | 435 |
| | 250 | 600 |

Space Storable Oxidizer Valve Test Parameters for Tests Conducted at
Inlet Pressure of 250 psig

The "better valve" from the preceeding test series, Enclosure (1), will be subjected to 750 LF₂ endurance cycles at an inlet pressure of 250 psig.

| <u>Parameter</u> | <u>750 Cycles</u> |
|--|---|
| Test Fluid | LF ₂ |
| Inlet Pressure (psig) | 250 $\begin{smallmatrix} +25 \\ -0 \end{smallmatrix}$ |
| Flow Rate (lb/sec) | 12 $\begin{smallmatrix} +1.0 \\ -0.5 \end{smallmatrix}$ |
| Maximum Pressure Drop at Rated Flow (psid) | 5 |
| Actuation Fluid | GH _e |
| Actuation Pressure (psig) | 500 \pm 15 |
| Pilot Valve Voltage (Vdc) | 28 \pm 2 |
| Proximitior Voltage (Vdc) | -28 \pm 0.1 |
| Potentiometer Voltage (Vdc) | 5 \pm 0.1 |
| Leakage Tests at (No. Cycles) | 300, 400, 600, 800, 1000 |
| Exposure Flow Time, Min. (sec) | 600* |

| <u>*Exposure Flow Time at Leakage Tests, Min (Sec)</u> | <u>Cycles</u> | <u>Exposure Time</u> |
|--|---------------|----------------------|
| | 250 (ref) | 600 (ref) |
| | 300 | 640 |
| | 400 | 710 |
| | 600 | 880 |
| | 800 | 1010 |
| | 1000 | 1200 |

APPENDIX B

NASA CR-72691 DISTRIBUTION LIST

Report
Copies

R D

Recipient

Designee

National Aeronautics & Space Administration
Lewis Research Center
21000 Brookpark Road
Cleveland, Ohio 44135

1 Attn: Contracting Officer, MS 500-313
5 Liquid Rocket Technology Branch, MS 500-209
1 Technical Report Control Office, MS 5-5
1 Technology Utilization Office, MS 3-16
2 AFSC Liaison Office, 501-3
2 Library
1 Office of Reliability & Quality Assurance,
MS 500-111
1 D. L. Nored, Chief, LRTB, MS 500-209
5 R. E. Grey Project Manager, 500-209
1 E. W. Conrad, MS 500-204

1 J. W. Gregory, MS 500-209
1 W. R. Dunbar MS 500-106

2 Chief, Liquid Experimental Engineering, RPX
Office of Advanced Research & Technology
NASA Headquarters
Washington, D.C. 20546

2 Chief, Liquid Propulsion Technology, RPL
Office of Advanced Research & Technology
NASA Headquarters
Washington, D.C. 20546

1 Director, Launch Vehicles & Propulsion, SV
Office of Space Science & Applications
NASA Headquarters
Washington, D.C. 20546

1 Chief, Environmental Factors & Aerodynamics
Code RV-1
Office of Advanced Research & Technology
NASA Headquarters
Washington, D.C. 20546

1 Chief, Space Vehicles Structures
Office of Advanced Research & Technology
NASA Headquarters
Washington, D.C. 20546

| Report Copies | <u>Recipient</u> | <u>Designee</u> |
|------------------|---|--|
| <u>R D</u> | | |
| 1 | Director,, Advanced Manned Missions, MT Office of Manned Space Flight NASA Headquarters Washington, D.C. 20546 | |
| 2 | NASA Scientific & Technical Information Facility P.O. Box 33 College Park, Maryland 20740 | |
| 1 | Director, Technology Utilization Division Office of Technology Utilization NASA Headquarters Washington, D.C. 20546 | |
| 1 | National Aeronautics & Space Administration Ames Research Center Moffett Field, California 94035 Attn: Library | Hans M. Mark Mission Analysis Division |
| 1 | National Aeronautics & Space Administration Flight Research Center P.O. Box 273 Edwards, California 93523 Attn: Library | |
| 1 | National Aeronautics & Space Administration Goddard Space Flight Center Greenbelt, Maryland 20771 Attn: Library | Merland L. Moseson Code 620 |
| 1 | National Aeronautics & Space Administration John F. Kennedy Space Center Cocoa Beach, Florida 32931 Attn: Library | Dr. Kurt H. Debus |
| 1 | National Aeronautics & Space Administration Langley Research Center Langley Station Hampton, Virginia 23365 Attn: Library | E. Cortwright Director |

Report
Copies

| <u>R</u> | <u>D</u> | <u>Recipient</u> | <u>Designee</u> |
|----------|----------|--|--|
| 3 | | National Aeronautics & Space Administration Manned Spacecraft Center Houston, Texas 77001 Attn: Library Charles Yodzis Code EP-2 Henry Pohl Code EP-4 | J. G. Thiobodaux Chief, Propulsion & Power Division |
| 4 | | National Aeronautics & Space Administration George C. Marshall Space Flight Center Huntsville, Alabama 35812 Attn: Library Jerry Thomson, PD-RV John McCarty, R-P&VE Charlie Johnston, PD-RV-V | Hans G. Paul Leon J. Hastings James Thomas Dale Burrows I. G. Yates Clyde Nevins J. Blumrich |
| 1 | | Jet Propulsion Laboratory 4800 Oak Grove Drive Pasadena, California 91103 Attn: Library | Henry Burlage, Jr. Duane Dipprey |
| 1 | | Defense Documentation Center Cameron Station Building 5 5010 Duke Street Alexandria, Virginia 22314 Attn: TISIA | |
| 1 | | Office of the Director of Defense Research & Engineering Washington, D.C. 20301 Attn: Office of Asst. Dir. (Chem. Technology) | |
| 1 | | RTD (RTNP) Bolling Air Force Base Washington, D.C. 20332 | |
| 1 | | Arnold Engineering Development Center Air Force Systems, Command Tullahoma, Tennessee 37389 Attn: Library | Dr. H. K. Doetsch |
| 1 | | Advanced Research Projects Agency Washington, D.C. 20525 Attn: Library | |

Report
Copies
R D

Recipient

Designee

| | | |
|---|--|--------------------------------|
| 1 | Aeronautical Systems Division Air Force Systems Command Wright-Patterson Air Force Base, Dayton, Ohio Attn: Library | D. L. Schmidt Code ARSCNC-2 |
| 1 | Air Force Missile Test Center Patrick Air Force Base, Florida Attn: Library | L. J. Ullian |
| 1 | Air Force Systems Command Andrews Air Force Base Washington, D.C. 20332 Attn: Library | Capt. S. W. Bowen SCLT |
| 2 | Air Force Rocket Propulsion Laboratory (RPR) Edwards, California 93523 Attn: Library Tom Waddell - RPRPD | Robert Wiswell W. W. Wells |
| 1 | Air Force Rocket Propulsion Laboratory (RPM) Edwards, California 93523 Attn: Library | |
| 1 | Air Force FTC (FTAT-2) Edwards Air Force Base, California 93523 Attn: Library | Donald Ross |
| 1 | Air Force Office of Scientific Research Washington, D.C. 20333 Attn: Library | SREP, Dr. J. F. Masi |
| 1 | Space & Missile Systems Organization Air Force Unit Post Office Los Angeles, California 90045 Attn: Technical Data Center | |
| 1 | Office of Research Analyses (OAR) Holloman Air Force Base, New Mexico 88330 Attn: Library RRRD | |

Report
Copies

| <u>R</u> | <u>D</u> | <u>Recipient</u> | <u>Designee</u> |
|----------|----------|---|--|
| 1 | | U.S. Air Force Washington, D.C. Attn: Library | Col. C. K. Stambaugh, Code AFRST |
| 1 | | Commanding Officer U.S. Army Research Office (Durham) Box CM, Duke Station Durham, North Carolina 27706 Attn: Library | |
| 1 | | U.S. Army Missile Command Redstone Scientific Information Center Redstone Arsenal, Alabama 35808 Attn: Document Section | Dr. W. Wharton / |
| 1 | | Bureau of Naval Weapons Department of the Navy Washington, D.C. Attn: Library | J. Kay, Code RTMS-41 |
| 1 | | Commander U.S. Naval Missile Center Point Mugu, California 93041 Attn: Technical Library | |
| 1 | | Commander U.S. Naval Weapons Center China Lake, California 93557 Attn: Library | |
| 1 | | Commanding Officer Naval Research Branch Office 1030 E. Green Street Pasadena, California 91101 Attn: Library | |
| 1 | | Director (Code 6180) U.S. Naval Research Laboratory Washington, D.C. 20390 Attn: Library | H. W. Carhart J. M. Krafft |
| 1 | | Picatinny Arsenal Dover, New Jersey 07801 Attn: Library | I. Forsten |

Report
Copies
R D

Recipient

Designee

| | | |
|---|--|-------------------------------|
| 1 | Air Force Aero Propulsion Laboratory Research & Technology Division Air Force Systems Command United States Air Force Wright-Patterson AFB, Ohio 45433 Attn: APRP (Library) | R. Quigley C. M. Donaldson |
| 1 | Electronics Division Aerojet-General Corporation P.O. Box 296 Azusa, California 91703 Attn: Library | W. L. Rogers |
| 1 | Space Division Aerojet-General Corporation 9200 East Flair Drive El Monte, California 91734 Attn: Library | S. Machlawski |
| 1 | Aerojet Ordnance and Manufacturing Aerojet-General Corporation 11711 South Woodruff Avenue Fullerton, California 90241 Attn: Library | |
| 1 | Aerojet Liquid Rocket Company P.O. Box 15847 Sacramento, California 95813 Attn: Technical Library 2484-2015A | R. Stiff C. W. Williams |
| 1 | Aeronutronic Division of Philco Ford Corp. Ford Road Newport Beach, California 92663 Attn: Technical Information Department | Dr. L. H. Linder |
| 1 | Aerospace Corporation 2400 E. El Segundo Blvd. Los Angeles, California 90045 Attn: Library-Documents | J. G. Wilder W. Wetmore |
| 1 | Arthur D. Little, Inc. 20 Acorn Park Cambridge, Massachusetts 02140 Attn: Library | A. C. Tobey |

| Report Copies | Recipient | Designee |
|------------------|---|---|
| <u>R D</u> | | |
| 1 | Astropower Laboratory McDonnell-Douglas Aircraft Company 2121 Paularino Newport Beach, California 92163 Attn: Library | |
| 1 | ARO, Incorporated Arnold Engineering Development Center Arnold AF Station, Tennessee 37389 Attn: Library | |
| 1 | Susquehanna Corporation Atlantic Research Division Shirley Highway & Edsall Road Alexandria, Virginia 22314 Attn: Library | |
| 1 | Beech Aircraft Corporation Boulder Facility Box 631 Boulder, Colorado Attn: Library | Douglas Pope |
| 1 | Bell Aerosystems, Inc. Box 1 Buffalo, New York 14240 Attn: Library | T. Reinhardt W. M. Smith J. R. Flanagan |
| 1 | Instruments & Life Support Division Bendix Corporation P.O. Box 4508 Davenport, Iowa 52808 Attn: Library | W. M. Carlson |
| 1 | Bellcomm 955 L'Enfant Plaza, S. W. Washington, D.C. Attn: Library | H. S. London C. Bendersky |
| 1 | Boeing Company Space Division P.O. Box 868 Seattle, Washington 98124 Attn: Library | J. D. Alexander C. F. Tiffany |

| Report Copies | | <u>Recipient</u> | <u>Designee</u> |
|------------------|----------|--|-----------------|
| <u>R</u> | <u>D</u> | | |
| 1 | | Boeing Company 1625 K Street, N.W. Washington, D.C. 20006 | |
| 1 | | Boeing Company P.O. Box 1680 Huntsville, Alabama 35801 | Ted Snow |
| 1 | | Chemical Propulsion Information Agency Applied Physics Laboratory 8621 Georgia Avenue Silver Spring, Maryland 20910 | Tom Reedy |
| 1 | | Chrysler Corporation Missile Division P.O. Box 2628 Detroit, Michigan Attn: Library | John Gates |
| 1 | | Chrysler Corporation Space Division P.O. Box 29200 New Orleans, Louisiana 70129 Attn: Librarian | |
| 1 | | Curtiss-Wright Corporation Wright Aeronautical Division Woodridge, New Jersey Attn: Library | G. Kelley |
| 1 | | University of Denver Denver Research Institute P.O. Box 10127 Denver, Colorado 80210 Attn: Security Office | |
| 1 | | Fairchild Stratos Corporation Aircraft Missiles Division Hagerstown, Maryland Attn: Library | |
| 1 | | Research Center Fairchild Hiller Corporation Germantown, Maryland Attn: Library | Ralph Hall |

Report
Copies

| <u>R</u> | <u>D</u> | <u>Recipient</u> | <u>Designee</u> |
|----------|----------|--|-----------------------------|
| 1 | | Republic Aviation Fairchild Hiller Corporation Farmington, Long Island New York | |
| 1 | | General Dynamics/Convair P.O. Box 1128 San Diego, California 92112 Attn: Library | Frank Dore R. Nau |
| 1 | | Missiles and Space Systems Center General Electric Company Valley Forge Space Technology Center P.O. Box 8555 Philadelphia, Pa. 19101 Attn: Library | A. Cohen F. Schultz |
| 1 | | General Electric Company Flight Propulsion Lab. Department Cincinnati, Ohio Attn: Library | D. Suichu Leroy Smith |
| 1 | | Grumman Aircraft Engineering Corporation Bethpage, Long Island, New York Attn: Library | Joseph Gavin R. Grossman |
| 1 | | Hercules Powder Company Allegheny Ballistics Laboratory P.O. Box 210 Cumberland, Maryland 21501 Attn: Library | |
| 1 | | Honeywell Inc. Aerospace Division 2600 Ridgeway Road Minneapolis, Minnesota Attn: Library | |
| 1 | | IIT Research Institute Technology Center Chicago, Illinois 60616 Attn: Library | C. K. Hersh |

Report
Copies

R D

Recipient

Designee

| | | |
|---|---|--|
| 1 | Kidde Aer-Space Division Walter Kidde & Company, Inc. 567 Main Street Belleville, New Jersey | R. J. Hanville |
| 1 | Ling-Temco-Vought Corporation P.O. Box 5907 Dallas, Texas 75222 Attn: Library | |
| 1 | Lockheed Missiles and Space Company P.O. Box 504 Sunnyvale, California 94087 Attn: Library | W. Sterbentz |
| 1 | Lockheed Propulsion Company P.O. Box 111 Redlands, California 92374 Attn: Library, Thackwell | H. L. Thackwell |
| 1 | Marquardt Corporation 16555 Saticoy Street Box 2013 - South Annex Van Nuys, California 91409 | Irv. Glasser T. Hudson |
| 1 | Martin-Marietta Corporation (Baltimore Division) Baltimore, Maryland 21203 Attn: Library | |
| 1 | Denver Division Martin-Marietta Corporation P.O. Box 179 Denver, Colorado 80201 Attn: Library | Dr. Morganthaler F. R. Schwartzber J. McCown |
| 1 | Orlando Division Martin-Marietta Corporation Box 5827 Orlando, Florida Attn: Library | J. Fern |

| Report Copies | | <u>Recipient</u> | <u>Designee</u> |
|-------------------|--|---|---|
| <u>R</u> <u>D</u> | | | |
| 1 | | Western Division McDonnell Douglas Astronautics 5301 Bolsa Avenue Huntington Beach, California 92647 Attn: Library | R. W. Hallet G. W. Burge P. Klevatt R. J. Gunkel |
| 1 | | McDonnell Douglas Aircraft Corporation P.O. Box 516 Lambert Field, Missouri 63166 Attn: Library | R. A. Herzmark D. Stone |
| 1 | | Rocketdyne Division North American Rockwell Inc. 6633 Canoga Avenue Canoga Park, California 91304 Attn: Library, Department 596-306 | Dr. R. J. Thompson S. F. Iacobellis S. Domokos |
| 1 | | Space & Information Systems Division North American Rockwell 12214 Lakewood Blvd. Downey, California Attn: Library | Dr. L. A. Harris |
| 1 | | Northrop Space Laboratories 3401 West Broadway Hawthorne, California Attn: Library | Dr. William Howard |
| 1 | | Purdue University Lafayette, Indiana 47907 Attn: Library (Technical) | Dr. Bruce Reese |
| 1 | | Radio Corporation of America Astro-Electronics Products Princeton, New Jersey Attn: Library | |
| 1 | | Rocket Research Corporation Willow Road at 116th Street Redmond, Washington 98052 Attn: Library | F. McCullough, Jr. |

Report
Copies
R D

Recipient

Designee

| | | |
|---|--|---|
| 1 | Stanford Research Institute 333 Ravenswood Avenue Menlo Park, California 94025 Attn: Library | Dr. Gerald Marks |
| 1 | Thiokol Chemical Corporation Redstone Division Huntsville, Alabama Attn: Library | John Goodloe |
| 1 | TRW Systems Inc. 1 Space Park Redondo Beach, California 90278 Attn: Tech. Lib. Doc. Acquisitions | D. H. Lee H. Burge |
| 1 | TRW TAPCO Division 23555 Euclid Avenue Cleveland, Ohio 44117 | P. T. Angell |
| 1 | United Aircraft Corporation Corporation Library 400 Main Street East Hartford, Connecticut 06108 Attn: Library | Dr. David Rix Erle Martin Frank Owen Wm. E. Taylor |
| 1 | United Aircraft Corporation Pratt & Whitney Division Florida Research & Development Center P.O. Box 2691 West Palm Beach, Florida 33402 Attn: Library | R. J. Coar Dr. Schmitke Paul Nappi |